



Enhancing our communities







45 Cindy Lane, Adjala-Tosorontio

HYDROGEOLOGICAL ASSESSMENT

2834556 Ontario Inc.

Document Control

File:	Prepared by:	Prepared for:
423499	Tatham Engineering Limited	2834556 Ontario Inc.
	645 Veterans Drive, Unit D	45 Cindy Lane
Date:	Barrie, Ontario L4N 9H8	New Tecumseth, Ontario L0M 1M0
August 26, 2024	T 705-733-9037	
	tathameng.com	

Authored by:	Reviewed by:
 Shane Mariner, B.Sc. (Env) Geoscience Intern	  Alicia Kimberley, P.Geo Group Leader - Hydrogeology
 Kimberly Gardner, B.Eng. EIT Project Manager	

Disclaimer	Copyright
The information contained in this document is solely for the use of the Client identified on the cover sheet for the purpose for which it has been prepared and Tatham Engineering Limited undertakes no duty to or accepts any responsibility to any third party who may rely upon this document.	This document may not be used for any purpose other than that provided in the contract between the Owner/Client and the Engineer nor may any section or element of this document be removed, reproduced, electronically stored or transmitted in any form without the express written consent of Tatham Engineering Limited.

Issue	Date	Description
1	August 26, 2024	Final Report

Document Contents

1	Introduction	1
1.1	Purpose and Scope of Work	1
1.2	Regulatory Requirements.....	3
2	Site Setting.....	4
2.1	Physiography, Surficial and Bedrock Geology	4
2.2	Topography, Drainage and Surface Water Features.....	4
2.3	Climate	4
2.4	MECP Water Well Records.....	5
2.5	Source Water Protection Mapping.....	6
2.6	Site Inspection	6
3	Procedures and Methodology	7
3.1	Door To Door Water Well Survey	7
3.2	Test Pitting.....	9
3.3	Water Supply Assessment	9
3.4	Long-Term Groundwater Level Monitoring	11
4	Subsurface Conditions	12
4.1	Stratigraphy	12
4.2	Groundwater	13
4.3	Infiltration Testing.....	14
4.4	Constant-Rate Pumping Test	15
5	Hydrogeological Discussion and Analysis.....	18
5.1	Water Balance	18
5.2	Low Impact Development Feasibility Assessment	18
5.3	Water Supply Assessment	18



5.4 Private Onsite Sewage Assessment.....21

6 References..... 24

Tables

Table 1: Summary of Domestic Water Well Survey 7
 Table 2: Test Pit Stratigraphy 12
 Table 3: Piezometer and Test Well Installation Details 13
 Table 4: Stabilized Groundwater Level Measurements 14
 Table 5: Guelph Permeameter Testing Results 15
 Table 6: Summary of Transmissivity 17

Figures

Figure 1: Site Location Plan 25
 Figure 2: Monitoring Location Plan 26
 Figure 3: MECP Water Well Locations 27
 Figure 4: Well Head Protection Area..... 28
 Figure 5: Intake Protection Zones 29
 Figure 6: Significant Groundwater Recharge Area 30
 Figure 7: Highly Vulnerable Aquifer 31
 Figure 8: Groundwater Contour 32

Appendices

- Appendix A: Water Balance Calculations
- Appendix B: MECP Water Well Records
- Appendix C: Test Well Construction Records
- Appendix D: Pumping Test Results
- Appendix E: Laboratory Certificates of Analysis
- Appendix D: Nitrate Impact Assessment



1 Introduction

Tatham Engineering Limited (Tatham) has been retained by 2834556 Ontario Inc. (the Client) to complete a Hydrogeological Assessment in accordance with the Ministry of Environment, Conservation and Parks (MECP) Guidelines D-5-4 and D-5-5 requirements for the proposed residential development located at 45 Cindy Lane in the Township of Adjala-Tosorontio, hereafter referred to as the “site”.

The subject property is comprised of 25.5 hectares (ha) (63.1 acres); however, the developable area of the property is comprised of approximately 3 ha (7.4 acres) of vacant/undeveloped land. For this investigation, the developable area of the property is considered the “site” and is referred to throughout this report. The surrounding lands to the east, west and south are primarily used for residential purposes with agricultural/vacant lands intermixed and the surrounding lands to the north are used for commercial purposes as the Silver Brook Golf Course. The site is bounded by Cindy Lane to the south, a tributary of Pine River to the north, a residential dwelling to the west and the entrance to the Silver Brook Golf Course to the east. A site location plan and monitoring location plan are enclosed as Figure 1 and 2, respectively.

The proposed residential development consists of eight separate lots, each with a private on-site water supply well and septic system. It is our understanding this project will proceed through concurrent Official Plan Amendment (OPA), Zoning By-Law Amendment (ZBA) and Draft Plan of Subdivision (Draft Plan) applications. As part of the on-going site plan development, a hydrogeological assessment was completed to assess the feasibility of the proposed individual on-site sewage systems and private water supply wells in accordance with MECP guidelines D-5-4 and D-5-5. Further, the hydrogeological assessment was also carried out in accordance with typical Nottawasaga Valley Conservation Authority (NVCA) and MECP hydrogeological requirements.

1.1 PURPOSE AND SCOPE OF WORK

The main objectives of the Hydrogeological Assessment were to:

- Establish local and regional geology and hydrogeology;
- Establish the soil and groundwater conditions on-site including infiltration potential and seasonal high groundwater levels;
- Verify the presence of existing water supply wells on-site and within 250-m radius of the site;



- Qualitatively assess the potential impacts to the nearby structures, water bodies and water users, if any, and comment on future regulatory agency involvement;
- Establish a pre and post construction water balance;
- Assess the feasibility of private water and/or septic servicing on-site; and
- Prepare a Hydrogeological Assessment report.

To achieve the above objectives, Tatham has proposed the following scope of work;

- Complete a desktop review of pertinent geological and hydrogeological resources, MECP water well records, previous geotechnical reports completed by others, if any, and proposed site plan drawings;
- Complete a door-to-door water well survey for residences within 250 m of the site to confirm the presence and usage of private water wells;
- Visit the site to note existing site conditions, topography, drainage, water features, neighboring land uses, and/or existing water supply or monitoring wells;
- Advance three test pits up to a depth of 3.0 m to facilitate Guelph Permeameter (GP) testing at approximate depths of 1.5 and 3.0 m in each test pit to evaluate in-situ filtration parameters;
- Install a mini piezometer and automatic dataloggers in each of the test pits and visit the site every 4 months for a 12-month period to facilitate long-term groundwater level monitoring;
- In accordance with MECP Guideline D-5-5 requirements, proposed developments 15 hectares or less in size require the installation and testing of at least three wells to assess the feasibility of private water supply. As such, the scope includes the installation and development of three 6" domestic water supply wells on-site;
- Complete a 6-hr constant rate pumping test in each of the three newly installed/developed residential supply wells;
- Determine baseline groundwater quality within the newly installed/developed residential supply wells to assess groundwater potability;
- Complete a desktop reasonable use assessment (nitrate impact assessment) and phosphorous assessment to confirm the feasibility of individual private septic systems; and
- Prepare a Hydrogeological Assessment Report in general accordance with the applicable MECP guidelines D-5-5 and D-5-4, and NVCA requirements.



1.2 REGULATORY REQUIREMENTS

1.2.1 Private On-Site Servicing

Residential developments to be reliant on private individual water supply wells and/or septic systems are to adhere to the following regulatory requirements:

- MECP D-5-5: Private Wells: Water Supply Assessment
- MECP D-5-4: Individual On-site Sewage Systems

This hydrogeological assessment will generally follow the above noted regulatory requirements; however, additional investigations and/or assessments may be required as part of the on-going OPA, ZBA and/or Draft Plan applications.



2 Site Setting

The site is located at 45 Cindy Lane in the Township of Adjala-Tosorontio, County of Simcoe. The site is approximately 3 hectares (7.4 acres) in size and is currently undeveloped/vacant. The site is bounded to the north and east by Silver Brook Golf Club, to the south by Cindy Lane and to the west by an existing residential property. The surrounding lands are primarily used for residential and commercial (golf course) purposes with agricultural/vacant lands intermixed.

2.1 PHYSIOGRAPHY, SURFICIAL AND BEDROCK GEOLOGY

The site lies within the physiographic region known as the Simcoe Lowlands, comprised of sand plains and beaches (Chapman and Putnam, 1984). Ontario Geological Survey (OGS) quaternary geology mapping indicates the site consists of glaciofluvial outwash deposits comprised of primarily gravel and sand. Bedrock beneath the site consists of Lindsay Formation limestone, dolostone and/or shale of the Simcoe Group.

These findings are consistent with the sandy subsurface conditions encountered during the installation of test wells completed by Highland Water Well Drilling Inc. as part of this hydrogeological assessment.

2.2 TOPOGRAPHY, DRAINAGE AND SURFACE WATER FEATURES

The topography of the site is relatively flat with elevations ranging from approximately 229 metres above sea level (masl) to 232 masl.

No water bodies are present within the site; however, a tributary of the Pine River is located north adjacent to the site and flows in a northeasterly direction. It is assumed on-site drainage will follow local surface topography and flow to the east/northeast, toward the tributary.

2.3 CLIMATE

Climate normal data between 1981 and 2010 was reviewed from the closest Environment Canada Climate Station to the site; Ruskview (Climate ID: 614722), located approximately 12.75 km to the west. The highest daily average temperature occurred in July, at 19.7°C, and the lowest occurred in January, at -7.3°C. The yearly average temperature between 1981 to 2010 was 6.5°C. The average total annual precipitation recorded was 996 mm. Climate data is tabulated in Appendix A.

In accordance with the Thornthwaite and Mather method, a water surplus of 507.2 mm/year was calculated for the site. Detailed calculations are provided in Appendix A for reference.



The infiltration from the annual surplus can be estimated based on infiltration factors from Table 3.1 of the SWM Planning and Design Manual (Ministry of Environment, 2003). Specific infiltration factors are provided for topography, soils, and land cover.

Topography.....	0.3
Soils.....	0.2
Land Cover.....	0.1
Total.....	0.6

For the purpose of this assessment, an infiltration factor of 0.6 was assumed for the site, resulting in an annual infiltration rate of 304.3 mm/year.

2.4 MECP WATER WELL RECORDS

To assess the nature of groundwater resources as well as the history of well usage within the area, MECP water well records were reviewed for a 500 m radius surrounding the site. The approximate locations of the MECP water wells are presented in Figure 3, and a summary of the MECP water wells is provided in Appendix B.

A total of 57 well records were reviewed within a 500 m radius of the site. Of the 57 well records, 53 indicated domestic supply well use, one indicated domestic supply and irrigation use, one indicated public supply well use and one indicated commercial supply well use. The remaining one well record did not indicate its use type.

In general, stratigraphy noted from the well records consisted of sandy silt or silt overlying layers of clay or silt with variable sand contents, overlying sand. Limestone bedrock was encountered at depths of approximately 69 to 70 m below ground surface (m bgs).

The majority of water wells were screened within the overburden sand unit at depths ranging between approximately 16 to 62 m bgs. Fresh water was encountered at depths ranging between approximately 2 to 71 m bgs, and gas was encountered locally at one location at a depth of 70 m bgs. Pumping test details were reviewed for available water wells records and indicated tests were carried out for 30 minutes to 7 hours at rates of 2.5 to 25 US gal/min (9.5 to 95 L/min) with 0.9 to 43 m of drawdown observed.

One well is present on the subject property and appears to be used at the Silver Brook Golf Club, just north of the site. The well record (MECP well record A000725) was reviewed. Based on the water well record the following is noted:

- The well included the installation of a 6.25" diameter steel casing to a depth of 41.1 m and a 5.75" stainless steel 18-slot screen within the confined sand aquifer at a depth of 41.3 to 44.5 m. During drilling, fresh water was encountered at a depth of 35.4 m, and following well



installation the static water level was noted at 7.0 m. A 1-hr and 50 min pumping test was carried out at a pumping rate of 139 L/min and 1.3 m of drawdown was noted at the end of the test. It was recommended the water well pump be installed at a depth of 30 m and a pumping rate of 450 L/min be utilized.

2.5 SOURCE WATER PROTECTION MAPPING

The site lies within the Nottawasaga Valley Source Protection Area (SPA). The site does not lie within a Well Head Protection Area (WHPA) nor Intake Protection Zone (IPZ), as shown on Figures 4 and 5, respectively. Further, the site does not lie within a Highly Vulnerable Aquifer (HVA), as shown on Figure 6, but does lie within a Significant Groundwater Recharge Area (SGRA) as shown on Figure 7.

2.6 SITE INSPECTION

A visual inspection of the site was conducted on May 7, 2024, to assess the site's drainage, topography and surface water features. The site consisted of approximately 3 hectares of undeveloped/vacant land just south of the Silver Brook Golf Club. The site was located in a primarily residential and commercial (golf course) area, with agricultural/undeveloped lands intermixed. No water bodies were present within the site; however, a tributary of Pine River is located north adjacent to the site. It is anticipated surface water runoff on site will follow local surface topography; draining into the Pine River tributary to the north of the Site.



3 Procedures and Methodology

3.1 DOOR TO DOOR WATER WELL SURVEY

Domestic water well surveys were distributed in May 2024 by Tatham representatives to all properties located partially or wholly within 250 m of the site. Based on the proximity to the site, a total of 27 properties were selected and included in the water well survey as summarized in Table 1, below.

Table 1: Summary of Domestic Water Well Survey

MUNICIPAL ADDRESS	RESPONSE TO WELL SURVEY	TYPE OF WELL	TERMINATION DEPTH OF WELL	STRATA SCREENED	ANY WATER QUALITY/ QUANTITY ISSUES?	TREATMENT
31 David Drive			No response at the time of report completion			
35 David Drive			No response at the time of report completion			
7186 Concession 3			No response at the time of report completion			
7121 Concession 3			No response at the time of report completion			
7135 Concession 3	Response provided vial mail	Drilled	37.5 m	Sand	No water quantity concerns. Water is hard and iron rich with slight sulfur odour	Water Softener
7151 Concession 3			No response at the time of report completion			
7191 Concession 3			No response at the time of report completion			
7093 Concession 3			No response at the time of report completion			
7077 Concession 3			No response at the time of report completion			
65 Cindy Lane	Response provided via phone	Assumed Dug	Unknown	Unknown	Utilizing Cistern	Unknown



MUNICIPAL ADDRESS	RESPONSE TO WELL SURVEY	TYPE OF WELL	TERMINATION DEPTH OF WELL	STRATA SCREENED	ANY WATER QUALITY/ QUANTITY ISSUES?	TREATMENT
64 Cindy Lane			No response at the time of report completion			
62 Cindy Lane			No response at the time of report completion			
60 Cindy Lane			No response at the time of report completion			
58 Cindy Lane			No response at the time of report completion			
56 Cindy Lane			No response at the time of report completion			
54 Cindy Lane			No response at the time of report completion			
52 Cindy Lane			No response at the time of report completion			
50 Cindy Lane			No response at the time of report completion			
48 Cindy Lane			No response at the time of report completion			
46 Cindy Lane			No response at the time of report completion			
44 Cindy Lane	Response provided via mail	Drilled	Assumed at approximately 36.6 m	Unknown	High Iron	Reverse osmosis system, iron filter and water softener
43 Cindy Lane			No response at the time of report completion			
41 Cindy Lane	Response provided via mail	Drilled	42.4 m	Sand	Water quality is poor, uses water treatment systems	UV filter and light, Reverse osmosis system, and water softener
39 Cindy Lane			No response at the time of report completion			



MUNICIPAL ADDRESS	RESPONSE TO WELL SURVEY	TYPE OF WELL	TERMINATION DEPTH OF WELL	STRATA SCREENED	ANY WATER QUALITY/ QUANTITY ISSUES?	TREATMENT
37 Cindy Lane	Response provided via mail	Drilled	38.7 m	Sand	Water is hard and iron rich	Water softener
35 Cindy Lane	No response at the time of report completion					
45 Cindy Lane - Clubhouse	No response at the time of report completion					

3.2 TEST PITTING

A test pitting program was carried out on May 7, 2024, following receipt of public and private underground utility service locates. The test pits were dug to depths of approximately 2.0 m bgs by an excavator provided and operated by Morris Shelswell & Sons Excavating. Tatham representatives examined and classified characteristics of the soils encountered in each of the test pits, noted groundwater conditions during and upon completion of the test pits, and reviewed all recovered soil samples.

Upon completion of the test pits, piezometers were installed in Test Pit 1 (TP1), TP2 and TP3 to allow for future groundwater level monitoring during subsequent pumping tests, as well as to facilitate long-term groundwater level monitoring.

3.3 WATER SUPPLY ASSESSMENT

In accordance with MECP guideline D-5-5 requirements, proposed developments which are 15 hectares or less in size require the installation and testing of at least three test wells to assess the feasibility of private water supply.

As such, three test wells (TW1, TW2, and TW3) were installed as part of this investigation. It is Tatham's understanding these three test wells are to be utilized as private domestic supply wells upon completion of the residential dwellings' construction.

3.3.1 Test Well Construction

TW1, TW2 and TW3 were installed by Highland Water Well Drilling Inc. (Highland) (MECP License #dd 2576) on May 1, 6 and 10, 2024, respectively, utilizing standard air rotary drilling methods (Well Tag No. A366563, A366566 and A366565, respectively). A copy of the water well records are provided in Appendix C.



A 6" steel casing water well was installed in all three wells. Wells TW2 and TW3 were installed with 5 ½" stainless-steel 12-slotted screens while TW1 was installed with a 5 ½" stainless-steel 16-slotted screen. All test wells were screened in the overburden sand unit from 39.9 to 41.1, 36.5 to 37.8, and 45.4 to 46.6 m bgs, respectively.

All wells were developed and chlorinated upon completion.

3.3.2 Constant Rate Pumping Test

Highland conducted 6-hour pumping tests concurrently on TW1 and TW3 on May 15, 2024, and TW2 on May 16, 2024, according to the MECP Guideline D-5-5. All test wells were pumped at a constant rate of 8 US gal/min (30.28 L/min) for the duration of the tests.

As part of the pumping tests, groundwater levels were manually measured by a Tatham representative before, during, and after the tests. Automatic dataloggers were used to measure continuous water levels throughout the tests. The results of the pumping tests and groundwater level monitoring are provided in Appendix D and are discussed further in Section 4.4.

3.3.3 Groundwater Sampling

During the 6-hour constant rate pump test, two representative groundwater samples were collected from TW1, TW2 and TW3 for a total of six samples. One sample was collected after the first hour of continuous pumping and another was collected within the final hour of continuous pumping. The samples were collected directly from the discharge pipe and were placed directly into pre-cleaned laboratory-supplied vials and/or bottles with analytical test group specific preservatives. Dedicated nitrile gloves were worn during sample collection and handling. The samples were submitted for chemical analysis of:

- One hour sample: chlorine (field test), E.coli, Total Coliform, Fecal Coliforms, background bacteria, nitrate, nitrite, sodium and turbidity.
- Final hour sample: chlorine (field test), E.coli, Total Coliform, Fecal Coliforms, background bacteria, nitrate, nitrite, sodium, turbidity, alkalinity, ammonia, calcium, chloride, color, conductivity, dissolved organic carbon, hardness, magnesium, manganese, pH, and total dissolved solids.

The analysis was compared to the Ontario Drinking Water Quality Standards (ODWQS). Samples were analyzed by Caduceon Environmental Laboratories, a CALA accredited laboratory in Barrie, Ontario. Groundwater chemistry results are included in the laboratory Certificates of Analysis, provided in Appendix E.



3.4 LONG-TERM GROUNDWATER LEVEL MONITORING

A long-term groundwater level monitoring program is being carried out in which groundwater levels within the three newly installed piezometers will be monitored for a 12-month period between May 2024 and April 2025. Groundwater levels will be continuously recorded by use of an automated datalogger recording device. Additionally, a Tatham representative will visit the site once every four months to confirm groundwater levels, for a total of three site visits.

A supplemental groundwater level letter will be prepared at the end of the long-term groundwater level monitoring program highlighting the seasonal high groundwater levels measured.



4 Subsurface Conditions

4.1 STRATIGRAPHY

A test pitting program was conducted on May 7, 2024, in which three test pits (TP1, TP2, and TP3) were advanced to approximate depths between 1.5 to 2.0 m bgs to facilitate GP testing and the installation of three piezometers. As part of the test pitting program, Tatham representatives examined and classified characteristics of the soils encountered in each of the test pits, noted groundwater conditions during and upon completion of the test pits, and reviewed all recovered soil samples.

In general, the test pits encountered topsoil overlying sand. Bedrock was not encountered in any of the test pits at termination depths.

The subsurface conditions encountered in TP1, TP2 and TP3 are summarized in Table 2, below:

Table 2: Test Pit Stratigraphy

TEST PIT LOCATION	UTM COORDINATES	SOIL STRATIGRAPHY	
TP1	17T 581739 m E 4898180 m N	0 to 0.50 m	Topsoil: dark brown, sand, organics, moist
		0.50 to 1.50 m	Sand: brown, fine sand, some silt, moist.
		1.50 m	Sand: grey, fine sand, wet
		TP Terminated	
TP2	17T 581626 m E 4898136 m N	0 to 0.30 m	Topsoil: dark brown, sand, organics, moist
		0.30 to 0.80 m	Sand: brown/orange/red, fine sand, moist
		0.80 to 1.00 m	Sand: brown/orange/red, fine sand, wet
		1.00 to 1.70 m	Sand: grey, find sand, trace gravel, wet
		TP Terminated	
TP3	17T 581435 m E	0 to 1.00 m	Topsoil: dark brown, sand, organics, moist



TEST PIT LOCATION	UTM COORDINATES	SOIL STRATIGRAPHY	
	4898095 m N	1.00 to 1.30 m	Sand: brown, fine sand, moist
		1.30 to 1.40 m	Sand: grey, fine sand, moist
		1.40 to 2.00 m	Sand: grey, fine sand, trace gravel, wet
		TP Terminated	

4.2 GROUNDWATER

4.2.1 Groundwater levels

A piezometer was installed at each test pit location to facilitate long-term groundwater level measurements of the shallow aquifer. The piezometers were installed with a slotted 1.0-meter-long screen.

A summary of the piezometers and on-site test well installation details and stabilized groundwater level measurements are provided below in Table 3 and 4, respectively.

Table 3: Piezometer and Test Well Installation Details

ID	GROUND SURFACE (m asl)	LOCATION OF SCREEN (Depth (m bgs) / Elevation (m asl))	STRATA SCREENED
TP1	229.9	0.5- 1.5 / 228.4 - 229.4	Fine sand
TP2	230.3	0.7 - 1.7 / 228.6 - 229.6	Fine sand, trace gravel
TP3	231.1	1.0 - 2.0 / 229.1 - 230.1	Fine sand, trace gravel
TW1	230.0	39.9 - 41.1 / 188.9 - 190.1	Sand
TW2	231.5	36.5 - 37.8 / 193.4 - 194.7	Sandy silt
TW3	231.5	45.4 - 46.6 / 184.9 - 186.1	Sand



Table 4: Stabilized Groundwater Level Measurements

ID	GROUND SURFACE* (M ASL)	GROUNDWATER LEVELS (m bgs / m asl)		
		MAY 15, 2024	MAY 16, 2024	MAY 22, 2024
TP1	229.9	0.5 / 229.4	0.5 / 229.4	0.4 / 229.5
TP2	230.3	0.3 / 230.0	0.4 / 229.9	0.5 / 229.8
TP3	231.1	0.2 / 230.9	0.3 / 230.8	0.3 / 230.8
TW1	230.0	5.1 / 224.9	5.1 / 224.9	-
TW2	231.5	4.8 / 226.7	4.8 / 226.7	-
TW3	231.5	3.3 / 228.2	3.3 / 228.2	-

Based upon the groundwater elevations to date, shallow groundwater levels range between 0.2 to 0.5 m bgs (elevation 229.4 to 230.9). It is anticipated shallow groundwater will follow surface topography and flow in a northeastern direction, toward the Pine River tributary as shown on Figure 8.

Regional groundwater is anticipated to flow to the northeast, ultimately flowing towards Nottawasaga River and Nottawasaga Bay.

4.3 INFILTRATION TESTING

4.3.1 Gradation Testing

Shallow soils on site are generally comprised of fine to coarse sands. Based on the Ontario Building Code (2012) Supplementary Standards S-6, typical percolation times of sands and silty fine sands range between 8 - 20 mins/cm and are considered to have medium to low permeability.

4.3.2 Guelph Permeameter Testing

Guelph Permeameter (GP) testing was completed to determine the average field saturated hydraulic conductivity (K_{fs}) of the on-site soils to assist in the preliminary design of LID features for the site and septic systems. GP tests were conducted at a depth of 0.5 m at TP1 and 0.7 m at TP2, in the dry conditions. GP tests were not completed at TP3 as the near surface soils were saturated. During each GP test, the water level within the GP chamber was visually monitored and recorded until a steady state infiltration rate was reached.



The field saturated hydraulic conductivity, K_{fs} , was determined using the Zhang et al. (1998) method as follows:

$$K_{fs} = \frac{CQ}{2\pi H^2 + \pi a^2 C + 2\pi \frac{H}{a^*}}$$

where:

C = shape factor

Q = the steady state rate of water level change (cm/s)

H = water head height (cm)

a = borehole radius (cm)

a^* = soil texture-structure category (cm^{-1})

The field saturated hydraulic conductivity value was then utilized to determine infiltration rates based on the method outlined in the Toronto Region Conservation Authority (TRCA) Low-Impact Development Stormwater Management Planning and Design Guide as follows:

$$\text{Infiltration Rate} = \sqrt[3.7363]{\frac{K_{fs}}{6 * 10^{-11}}}$$

The results of the Guelph Permeameter testing completed is summarized in Table 5, below.

Table 5: Guelph Permeameter Testing Results

TEST PIT LOCATION	TEST DEPTH (m)	STRATIGRAPHY TYPE	K_{fs} (cm/sec)	INFILTRATION RATE (mm/hr)	FACTORED INFILTRATION RATE (mm/hr)
TP1	0.5	Fine Sand	1.8×10^{-3}	101	40.4
TP2	0.7	Fine Sand	2.8×10^{-4}	61	24.5

4.4 CONSTANT-RATE PUMPING TEST

The results of the pumping tests and groundwater level monitoring are provided in Appendix D and summarized below.

4.4.1 TW1

The 6-hour constant pumping test was conducted at the same time as the 6-hour pumping test at TW3. The test well is terminated within the overburden sand unit at a depth of 41.1 m bgs. The pumping test was carried out at a rate of 30.3 L/min.



Groundwater Levels

During the pump test, water levels declined from a static level of 5.0 to 5.6 m bgs. The water levels recovered to within 5% of the static water level within 37 minutes.

At the end of the pump test, there was a total of 35.5 m of available drawdown.

Water Quality Results

Water samples were collected during the pumping test completed on TW1. Laboratory results indicated the 1-hour and 5-hour tests exceeded the Maximum Acceptable Concentration (MAC) for Total Coliform (<2 mg/L versus a limit of 0 mg/L). In addition, the 1-hour test exceeded the Aesthetic Objectives (AO) for turbidity (31.2 NTU versus a limit of 5 NTU) and the 5-hour test exceeded the Operational Guideline (OG) for Hardness as CaCO₃ (194 mg/L versus a limit of 100mg/L).

4.4.2 TW2

The test well is terminated within the overburden sand unit at a depth of 37.8 m bgs. The pumping test was carried out at a rate of 30.3 L/min.

Groundwater Levels

During the pump test, water levels declined from a static level of 4.8 to 8.2 m bgs. The water levels recovered to within 5% of the static water level within 11 minutes.

At the end of the pumping test, there was a total of 29.5 m of available drawdown

Water Quality Results

Water samples were collected during the pumping test completed on TW2. Laboratory results indicated the 1-hour and 5-hour tests exceeded the AO for turbidity (22.4 NTU and 7.2 NTU versus a limit of 5 NTU) and the MAC for Total Coliform (<2 mg/L and <2 mg/L versus a limit of 0 mg/L). In addition, the 5-hour test exceeded the OG for Hardness as CaCO₃ (199 mg/L versus a limit of 100mg/L).

4.4.3 TW3

The 6-hour pumping test was conducted at the same time as the 6-hour pumping test at TW1. The test well is terminated within the overburden sand unit at a depth of 46.6 m bgs. The pumping test was carried out at a rate of 30.3 L/min.



Groundwater Levels

During the pump test, water levels declined from a static water level of 3.3 to 22.0 m bgs. The water levels recovered to within 5% of the static water level within 4 hours.

At the end of the pump test, there was a total of 24.6 m of available drawdown.

Water Quality Results

Water samples were collected during the pumping test completed on TW3. Laboratory results indicated the 1-hour and 5-hour sample exceeded the AO for turbidity (82.7 NTU and 10.1 NTU versus a limit of 5 NTU) and the MAC for Total Coliform (<2 mg/L and 4 mg/L versus a limit of 0 mg/L). In addition, the 5-hour sample exceeded the OG for Hardness as CaCO₃ (168 mg/L versus a limit of 100 mg/L).

4.4.4 Calculated Transmissivity Values

The transmissivity was calculated utilizing the constant rate pump test results and the Jacob straight line method where:

$$T = \frac{2.3Q}{4\pi\Delta s}$$

Where,

Q = pumping rate (43.61 m³/day)

Δs = slope of the observed drawdown versus time for 1 log cycle (1.4 to 1.5 m)

Based on the above calculation, the transmissivity was calculated to be between 3.0 and 210 m²/day, as shown in Table 6, below.

Table 6: Summary of Transmissivity

ID	CALCULATED TRANSMISSIVITY (m ² /day)
TW1	210
TW2	88
TW3	3



5 Hydrogeological Discussion and Analysis

5.1 WATER BALANCE

An evaluation of the anticipated changes in the water balance between pre-development and post-development conditions has been included to quantify the expected changes to the water balance across the site with and without mitigation.

Using historical precipitation data from the Ruskview Climate Station (Climate ID: 614722) between 1981 and 2010, the pre-development water balance model shows a total of 9,129 m³ of annual infiltration volume is provided over the site area (3 ha). Given the current stage of planning, it was assumed the entire site would be developed for residential dwellings. Within each lot, it was assumed 13% of the post-development land cover would be considered impervious. As such, the post-development water balance assessment shows without mitigation, annual infiltration over the site may decrease by as much as 13%, corresponding to an annual infiltration reduction of 1,187 m³. Water balance calculations are provided in Appendix A for reference.

5.2 LOW IMPACT DEVELOPMENT FEASIBILITY ASSESSMENT

As discussed in previous sections, the site generally consists of sandy loamy topsoil overlying layers of fine sand with trace gravel. Groundwater is expected to be encountered at depths of 0.2 to 0.5 m bgs (elevation 229.4 to 230.9). Based on the groundwater conditions observed, infiltration-based LID features (such as infiltration chambers or soakaway pits) are not considered feasible for this site as the minimum separation distance (1.0 m) between the seasonally high groundwater table and the bottom of a proposed recharge facility cannot be satisfied.

5.3 WATER SUPPLY ASSESSMENT

5.3.1 Water Supply Potential - Quantity

In accordance with the MECPs D-5-5 guideline, a minimum daily water demand of 450 L/day/person, and a peak water demand of 3.75 L/min/person for a 120-minute period is to be assumed. The number of proposed bedrooms for the residences to be constructed on the property have not yet been determined, however, for the purposes of this assessment four bedroom and five persons per dwelling have been assumed. As such, a daily water demand of 2,250 L/day (1.56 L/min) and a peak water demand of 18.75 L/min are considered sufficient to yield an adequate water supply for the proposed residential dwellings.



It is noted, for a 3-hectare property, a minimum of three test wells are required to be constructed on-site and tested for at least 6 hours in accordance with the MECPs Guideline D-5-5.

A constant rate pumping test carried out on TW1 indicated a pumping rate of approximately 30.3 L/min could be sustained for 6-hours with a drawdown of 0.6 m noted. Further, following completion of the pumping test, recovery to within 5% of the original static water level was noted within 37 minutes.

A constant rate pumping test carried out on TW2 indicated a pumping rate of approximately 30.3 L/min could be sustained for 6-hours with a drawdown of 3.4 m noted. Further, following completion of the pumping test, recovery to within 5% of the original static water level was noted within 110 minutes.

A constant rate pumping test carried out on TW3 indicated a pumping rate of approximately 30.3 L/min could be sustained for 6-hours with a drawdown of 18.7 m noted. Further, following completion of the pumping test, recovery to within 5% of the original static water level was noted within 4 hours.

Considering the constant rate pumping tests resulted in 0.6 to 18.7 m of drawdown, corresponding to approximately 1.7% to 43% of the total available drawdown at a pumping rate of 30.3 L/min, it is considered feasible the peak water demand of 18.75 L/min could be achieved by the aquifer on-site.

It is recommended future wells on-site be installed within the same sand aquifer as TW1, TW2, and TW3. Assuming typical water usage and well separation, it is not anticipated the concurrent water taking from two individual water wells would adversely impact the available water supply given such a relatively small percentage of the total available drawdown is actually being utilized. In addition, the pumping tests at TW1 and TW3 were conducted concurrently, and water levels were continuously monitored in TW2 during the test to observe the impacts on neighboring wells. A total drawdown of 0.1 m was observed over the 6-hr pumping test at TW2, indicating minimal impacts to the neighboring wells.

All future water wells on-site should be installed and tested by a licensed water well contractor in accordance with O.Reg.903.

5.3.2 Water Supply Potential - Quality

Water quality samples were collected from TW1, TW2 and TW3 after the first hour of continuous pumping and within the final hour of continuous pumping. The samples indicated generally potable groundwater on-site with minor exceedances of turbidity (7.2 to 10.1 NTU, limit of 5 NTU), total coliform (<2 to 4 CFU/100mL, limit of 0 CFU/100mL), and hardness as CaCO₃ (168 to 199 mg/L, limit 100 mg/L).



The Aesthetic Objective (AO) for turbidity is set at 5 NTU (ODWQS, 2006). Turbidity is not a chemical parameter but rather a physical parameter; it is a measurement of the water's light scattering abilities. A high turbidity value would indicate a water sample which is cloudy or murky, while a low turbidity value would indicate a water sample which is clear, or transparent.

Turbidity is an important indicator of water treatment efficiency, especially filters. A significant relationship has been demonstrated between turbidity increases and the number of *Giardia* cysts and *Cryptosporidium* oocysts breaking through filters (MECP, 2006). Ontario Regulation 170/03 describes turbidity as posing a potential health risk within a drinking water system if the system is required to provide filtration, but when sampled, exceeds 1.0 NTU. Turbidity concentrations below 5 NTU are considered treatable.

The MAC for Total Coliform is set at 0 CFU/100mL (ODWQS, 2006). Total Coliform represents a group of bacteria which are typically found in soil and water which has been influenced by surface water and/or human/animal waste. The presence of coliform bacteria within drinking water can increase the risk of contracting a water-borne illness. The most common symptoms of contracting a water-borne illness include nausea, vomiting, and diarrhea. Infants, elderly people, and those with compromised immune systems are at the most risk. To kill microorganisms including coliform bacteria, water must be brought to and kept at a boil (100°C) for at least one continuous minute (New Brunswick, n.d.). Chlorination of the water wells prior to use and on a regular basis should be conducted to eliminate bacteria in the well.

The operational guideline for hardness is set between 80 to 100 mg/L (ODWQS, 2006). Hardness is caused by dissolved calcium and magnesium and is expressed as the equivalent quantity of calcium carbonate (CaCO_3). When heated, hard water tends to form scale deposits and can form excessive scum with regular soaps. However, there are certain detergents which are largely unaffected by hardness. Conversely, water too soft may result in accelerated corrosion of water pipes. Hardness levels between 80 and 100 mg/L as CaCO_3 is considered an acceptable balance between corrosion and incrustation. Water supplies with hardness greater than 200 mg/L are considered poor but tolerable. Hardness more than 500 mg/L in drinking water is unacceptable for most domestic purposes.

It is considered feasible groundwater found in the test wells on-site terminated between 38.7 and 46.6 m bgs will yield fresh water; however, future homeowners may wish to consider the implementation of conventional water treatment systems including water softeners, reverse osmosis systems and/or UV filters and lights.

Following the construction of future water wells on-site, each water well should be sampled to confirm potability in accordance with industry standards.



5.4 PRIVATE ONSITE SEWAGE ASSESSMENT

It is noted the MECP Guideline D-5-4 only applies to developments where average daily flows of less than 10,000 L/day are anticipated.

For the purposes of this assessment, a nitrate impact assessment (Steps 1 to 3) was carried out in accordance with MECP Guideline D-5-4.

5.4.1 Nitrate Impact Assessment

Step One: Lot Sizing

In accordance with MECP D-5-4, where individual lot sizes within a proposed development exceed 1 hectare (2.5 acre), the MECP considers the dilution of sewage effluent by infiltration precipitation to be adequate to reduce nitrate concentrations to acceptable levels. Assuming the site is not hydrogeologically sensitive, further assessments into the impact of septic systems are generally not required.

Based on the current design details, the lot sizes remain less than 1 hectare; thus, Tatham proceeds to Step Two.

Step Two: System Isolation

Where proposed lot sizes are less than 1 hectare, it is necessary to assess the potential risk of septic effluent on groundwater supplies. Where it can be demonstrated local water supplies are obtained from an aquifer at a depth hydraulically isolated from the sewage effluent in the receiving soil, further assessments are generally not required. The placement and sizing of the septic beds must take into consideration the minimum setback and separation distances outlined in O.Reg. 358 (Sewage Systems), O.Reg. 903 (Ontario Water Resources: Wells) and/or other municipal by-laws.

Where it cannot be demonstrated the sewage effluent is hydraulically isolated from the supply aquifer, Step 3 must be utilized.

Step 3 involves a hydrogeological study to evaluate the impact of infiltration of septic effluent from sewage treatments systems (nitrate loading considerations).

Although the on-site water wells are constructed in a deep confined aquifer, there is the possibility for shallow unconfined water wells to exist downgradient of the property. As such, Tatham proceeds to Step 3.

Step Three: Preliminary Nitrate Impact Assessment

Nitrate in septic effluent is attenuated by dilution with infiltrating water, water discharged into the septic bed, and groundwater seepage from the upstream to the downstream side of the



property (groundwater flux). For the purposes of this assessment, groundwater flux was not considered in the nitrate dilution calculation; as such, the nitrate loading assessment is considered conservative.

The nitrate concentration at the downgradient property line of the 3 ha property, assuming eight proposed residential lots without pre-treatment, was computed to be 9.78 mg/L, which meets the regulatory requirement maximum of 10 mg/L.

Detailed Calculations are provided in Appendix F.

5.4.2 Phosphorous Impact Assessment

In accordance with the MECP D-5-5 and MECP Design Guidelines for Sewage Works (2008): Chapter 11 - Large Subsurface Sewage Disposal Systems, when the discharge of sewage effluent and a surface water feature are within 300 m of each, the potential impact to surface water needs to be evaluated.

Based on the grades on-site, it is anticipated runoff and shallow groundwater will flow to the north to northeast towards the tributary of Pine River located north adjacent to the site which ultimately flows to the Nottawasaga River. As the private septic systems will fall within 300 m of the water body, a phosphorous assessment in addition to the above nitrate assessment was considered applicable.

The phosphorous mass loading from on-site septic systems were calculated assuming:

- Each septic system will generate 1,000 L/day of effluent, for a total of 8,000 L/day for the site (8 private septic systems).
- A 15 mg/L phosphorous loading concentration.

Based on the above the phosphorous loading was estimated to be 5.5 kg/year per individual septic system or 43.8 kg/year for the entire proposed development (8 lots).

Based on the anticipated phosphorous loading as a result of the proposed on-site septic systems it is recommended phosphorous removal be incorporated into the proposed septic system. Conventional clean sand leaching beds can remove between 15 to 35% of phosphorous, and advance treatments can remove up to 95%. Assuming a conventional clean sand leaching bed is utilized (35% reduction in phosphorous concentration) the resultant phosphorous loading is estimated to be 3.6 kg/year per individual septic system or 28.5 kg/year for the entire proposed development (8 lots).

The Nottawasaga Valley Conservation Watershed notes 47 tonnes (47,754 kg/year) of phosphorous enters the Nottawasaga River each year. The estimated phosphorous load 28.5 kg/year resulting from the proposed on-site septic systems represents 0.06% of the total



phosphorous level entering the Nottawasaga River. As such, the proposed development is considered to be a small contributor of phosphorous to the Nottawasaga River and the increased phosphorous loading as a result of the proposed developed is considered negligible.

A further phosphorous assessment has been completed as part of Tatham's Storm Water Management Report for the pre- and post-development land use activities and is reported separately.

5.4.3 Summary and Next Steps

The nitrate impact assessment confirms eight individual residential lots are feasible.

The near surface sandy soils on-site are anticipated to have percolation rates of 8 to 20 min/cm. Individual septic systems must be constructed above the annual high groundwater table. Groundwater is anticipated at depths as shallow as 0.2 m bgs (229.4 m asl). As such, raised septic systems will need to be considered if the minimum separation distance between the annual high groundwater table and the bottom of the septic system cannot be maintained, typically 0.9 m (OBC, 1997).

To reduce the anticipated phosphorous loadings it is recommended a convention clean sand filter bed be incorporated into the proposed septic system to achieve a 15-35% reduction in phosphorous.

It is noted septic systems will need to be designed by a licensed engineer or septic system designer in accordance with the applicable placement and sizing requirements as outlined in O.Reg. 358, O.Reg. 903, the Ontario Building Code, and other municipal considerations.



6 References

Chapman, L.J. and Putnam, D.F. 2007. The Physiography of Southern Ontario; Ontario Geological Survey, Miscellaneous Release – Data 228.

Ministry of Environment. March 2003. Stormwater Management Planning and Design Manual

New Brunswick Office of the Chief Medical Officer of Health (Public Health). Facts on Drinking Water, Coliform Bacteria – Total Coliforms & E.coli.

Ontario Building Code, O. Reg. 332/12, s.8.4.2.1. (1), 1997

Ontario Ministry of the Environment and Climate Change. Technical Support Document for Ontario Drinking Water Standards, Objectives and Guidelines. June 2006

Toronto and Region Conservation Authority. Stormwater Management Criteria. August 2012, version 1.0.

Ministry of Municipal Affairs and Housing Building and Development Branch, Ontario Building Code. MMAH Supplementary Standard SB-6. Percolation Time and Soil Descriptions. September 14, 2012.









NOTES:

- 1. COORDINATE SYSTEM: NAD 1983 UTM ZONE 17N
- 2. CONTAINS INFORMATION LICENSED UNDER THE OPEN GOVERNMENT LICENSE - ONTARIO.

LEGEND

-  SITE
-  SUBJECT LANDS
-  ROAD
-  WATERCOURSE
-  WATERBODY
-  WOODED AREA
-  CANADIAN FORCES BASE - BORDEN



45 CINDY LANE, ADJALA-TOSORONTIO
HYDROGEOLOGICAL SITE ASSESSMENT
SITE LOCATION PLAN

DWG. No.

FIG-1

SCALE: 1:15,000

DRAWN: AO

DATE: AUG. 2024







JOB NO. 423499





NOTES:

- 1. COORDINATE SYSTEM: NAD 1983 UTM ZONE 17N
- 2. CONTAINS INFORMATION LICENSED UNDER THE OPEN GOVERNMENT LICENSE - ONTARIO.

LEGEND

-  SITE
-  SUBJECT LANDS
-  TEST PIT LOCATIONS
-  TEST WELL LOCATIONS
-  ROAD
-  WATERCOURSE



**45 CINDY LANE, ADJALA-TOSORONTIO
HYDROGEOLOGICAL SITE ASSESSMENT
MONITORING LOCATION PLAN**

DWG. No.

FIG-2

SCALE: 1:3,500

DRAWN: AO

DATE: AUG. 2024

JOB NO. 423499














CANADIAN FORCES
BASE - BORDEN

NOTES:

- 1. COORDINATE SYSTEM: NAD 1983 UTM ZONE 17N
- 2. CONTAINS INFORMATION LICENSED UNDER THE OPEN GOVERNMENT LICENSE - ONTARIO.

LEGEND

-  SITE
-  SUBJECT LANDS
-  STUDY AREA (500m)
-  MECP WATER WELLS
-  ROAD
-  WATERCOURSE
-  WATERBODY
-  WOODED AREA
-  CANADIAN FORCES BASE - BORDEN



45 CINDY LANE, ADJALA-TOSORONTIO
HYDROGEOLOGICAL SITE ASSESSMENT
MECP WATER WELL RECORDS

DWG. No.

FIG-3

SCALE: 1:7,500

DRAWN: AO

DATE: AUG. 2024

JOB NO. 423499





CANADIAN FORCES
BASE - BORDEN

NOTES:

- 1. COORDINATE SYSTEM: NAD 1983 UTM ZONE 17N
- 2. CONTAINS INFORMATION LICENSED UNDER THE OPEN GOVERNMENT LICENSE - ONTARIO.

LEGEND

-  SITE
-  SUBJECT LANDS
-  WELLHEAD PROTECTION AREA
-  ROAD
-  WATERCOURSE
-  WATERBODY
-  WOODED AREA
-  CANADIAN FORCES BASE - BORDEN



**45 CINDY LANE, ADJALA-TOSORONTIO
HYDROGEOLOGICAL SITE ASSESSMENT
WELLHEAD PROTECTION AREA**

DWG. No.

FIG-4

SCALE: 1:6,000

DRAWN: AO









DATE: AUG. 2024



JOB NO. 423499



NOTES:
 1. COORDINATE SYSTEM: NAD 1983 UTM ZONE 17N
 2. CONTAINS INFORMATION LICENSED UNDER THE OPEN GOVERNMENT LICENSE - ONTARIO.

LEGEND

-  SITE
-  SUBJECT LANDS
-  INTAKE PROTECTION ZONE
-  ROAD
-  WATERCOURSE
-  WATERBODY
-  WOODED AREA
-  CANADIAN FORCES BASE - BORDEN



**45 CINDY LANE, ADJALA-TOSORONTIO
 HYDROGEOLOGICAL SITE ASSESSMENT
 INTAKE PROTECTION ZONE**

DWG. No.

FIG-5

SCALE: 1:6,000

DRAWN: AO

DATE: AUG. 2024









JOB NO. 423499





NOTES:

- 1. COORDINATE SYSTEM: NAD 1983 UTM ZONE 17N
- 2. CONTAINS INFORMATION LICENSED UNDER THE OPEN GOVERNMENT LICENSE - ONTARIO.

LEGEND

-  SITE
-  SUBJECT LANDS
-  HIGHLY VULNERABLE AQUIFER
-  ROAD
-  WATERCOURSE
-  WATERBODY
-  WOODED AREA
-  CANADIAN FORCES BASE - BORDEN



**45 CINDY LANE, ADJALA-TOSORONTIO
HYDROGEOLOGICAL SITE ASSESSMENT
HIGHLY VULNERABLE AQUIFER**

DWG. No.

FIG-6

SCALE: 1:6,000

DRAWN: AO

DATE: AUG. 2024









JOB NO. 423499





NOTES:

- 1. COORDINATE SYSTEM: NAD 1983 UTM ZONE 17N
- 2. CONTAINS INFORMATION LICENSED UNDER THE OPEN GOVERNMENT LICENSE - ONTARIO.

LEGEND

-  SITE
-  SUBJECT LANDS
-  SIGNIFIGANT GROUNDWATER RECHARGE AREA
-  ROAD
-  WATERCOURSE
-  WATERBODY
-  WOODED AREA
-  CANADIAN FORCES BASE - BORDEN



**45 CINDY LANE, ADJALA-TOSORONTIO
HYDROGEOLOGICAL SITE ASSESSMENT
SIGNIFICANT GROUNDWATER RECHARGE AREA**

DWG. No.

FIG-7

SCALE: 1:6,000

DRAWN: AO

DATE: AUG. 2024

JOB NO. 423499





NOTES:

- 1. COORDINATE SYSTEM: NAD 1983 UTM ZONE 17N
- 2. CONTAINS INFORMATION LICENSED UNDER THE OPEN GOVERNMENT LICENSE - ONTARIO.

LEGEND

- SITE
- SUBJECT LANDS
- TEST WELLS
- ROAD
- WATERCOURSE
- WATERBODY
- WOODED AREA
- GROUNDWATER CONTOUR
- GROUNDWATER FLOW DIRECTION
- GROUNDWATER ELEVATION (MEASURED MAY, 16, 2024)



**45 CINDY LANE, ADJALA-TOSORONTIO
HYDROGEOLOGICAL SITE ASSESSMENT
SHALLOW GROUNDWATER CONTOUR**

DWG. No.

FIG-8

SCALE: 1:2,000

DRAWN: AO

DATE: AUG. 2024

JOB NO. 423499

Appendix A: Water Balance Calculations

Project Details

45 Cindy Lane	423499
---------------	--------

Prepared By

SM	August 26, 2024
----	-----------------

Water Balance Details

Methodology	Thornthwaite Method
Climate Data & Source	Ruskview Climate Station Climate Normal Data for 1981 to 2010 (Environment Canada) 6147229
Thornthwaite Coefficient	1.043

Month	Temp (°C)	Precip (mm)	Heat Index	PET (mm)	Daylight Factor	Days	AET (mm)	Surplus (mm)	Deficit (mm)
Jan.	-7.3	85.6	0.0	0.0	0.77	31	0.0	85.6	0.0
Feb.	-6.8	69.8	0.0	0.0	0.87	28	0.0	69.8	0.0
Mar.	-1.9	68.0	0.0	0.0	1.00	31	0.0	68.0	0.0
Apr.	5.4	73.9	1.1	28.9	1.12	30	32.5	41.4	0.0
May	12.1	86.9	3.8	76.0	1.23	31	93.8	0.0	6.9
Jun.	17.4	90.8	6.6	112.4	1.29	30	145.0	0.0	54.2
Jul.	19.7	81.5	8.0	129.3	1.26	31	163.2	0.0	81.7
Aug.	18.8	79.4	7.4	113.8	1.17	31	132.7	0.0	53.3
Sep.	14.7	95.4	5.1	76.2	1.04	30	79.5	15.9	0.0
Oct.	7.9	83.3	2.0	36.2	0.92	31	33.1	50.2	0.0
Nov.	1.7	100.3	0.2	6.2	0.80	30	5.0	95.3	0.0
Dec.	-4.3	80.9	0.0	0.0	0.74	31	0.0	80.9	0.0
Total	6.450	996	34.3	579.0	-	365	684.6	507.2	196.0

Additional Notes

PET = Potential Evapotranspiration
AET = Actual Evapotranspiration

Equations

$$PET = 16 \left(\frac{L}{12} \right) \left(\frac{N}{30} \right) \left(\frac{10T_d}{I} \right)^\alpha \text{ Where}$$

PET is the estimated potential evapotranspiration (mm/month)

T_d is the average daily temperature (degrees Celsius; if this is negative, use 0) of the month being calculated

N is the number of days in the month being calculated

L is the average day length (hours) of the month being calculated

$$\alpha = (6.75 \times 10^{-7})I^3 - (7.71 \times 10^{-5})I^2 + (1.792 \times 10^{-2})I + 0.49239$$

$$I = \sum_{i=1}^{12} \left(\frac{T_{mi}}{5} \right)^{1.514} \text{ is a heat index which depends on the 12 monthly mean temperatures } T_{mi} \text{ [1]}$$

Water Budget

Project Details

45 Cindy Lane	423499
---------------	--------

Prepared By

SM	26-Aug-24
----	-----------

Pre-Development Catchment Details

Area (ha)	3.00
Pervious Area (ha)	3.00
Impervious Area (ha)	0.00

Post Development Catchment Details

Area (ha)	3.00
Pervious Area (ha)	2.61
Impervious Area (ha)	0.39

Infiltration Factor	Pre-Development			Post Development		
	Pervious	Impervious	Total	Pervious	Impervious	Total
Topography	0.300	0.0		0.300	0.0	
Soil	0.200	0.0		0.200	0.0	
Land Cover	0.100	0.0		0.100	0.0	
Infiltration Factor	0.600	0.0		0.600	0.0	

Water Budget	Pervious	Impervious	Total	Pervious	Impervious	Total
Water Surplus (m ³)	15,216	0	15,216	13,238	1,978	15,216
Infiltration (m ³)	9,129	0	9,129	7,943	0	7,943
Runoff (m ³)	6,086	0	6,086	5,295	1,978	7,273
Reduction in Infiltration Volume (m ³)						1,187
Reduction in Infiltration Volume (%)						13.0

<u>Topography</u>	Flat Land, average slope < 0.6 m/km	0.3
	Rolling Land, average slope 2.8 m to 3.8 m/km	0.2
	Hilly Land, average slope 28 m to 47 m/km	0.1
<u>Soils</u>	Tight impervious clay	0.1
	Medium combinations of clay and loam	0.2
	Open Sandy loam	0.4
<u>Cover</u>	Cultivated Land	0.1
	Woodland	0.2

Appendix B: MECP Water Well Records

Township Con Lot	UTM	Date Centr	Casing Dia	Water	Pump Test	Well Use	Screen Depth	Well	Formation
ADJALA TOWNSHIP	17 581358 4897991 W	2008/03 7219	6	FR 0151 GS 0230	13/70/2/1:0	PS		7103710 (Z76302) A071841	BRWN FSND SILT 0012 GREY FSND CLAY 0020 GREY FSND SILT 0050 GREY CLAY FSND 0110 GREY CLAY SAND GRVL 0152 GREY GRVL SILT FSND 0154 GREY CLAY GRVL MSND 0230 GREY LMSN 0253
TOSORONTIO TOWNSHIP 03 014	17 581912 4898302 W	2005/10 7178						5740233 (Z38644) A	
TOSORONTIO TOWNSHIP 03 016	17 581994 4898642 W	1986/12 4919	30	UK 0010	10/22//:30	DO		5721682 (NA)	BRWN LOAM HARD 0001 BRWN SAND LOOS 0020 GREY CLAY HARD 0028
TOSORONTIO TOWNSHIP 03 016	17 582035 4898596 W	1986/12 4919	30	UK 0010	10/22//:30	DO		5721681 (NA)	BRWN LOAM 0001 BRWN SAND LOOS 0020 GREY CLAY HARD 0028
TOSORONTIO TOWNSHIP 03 018	17 581594 4898054 W	2007/02 7219	6	FR 0118	17/29/12/3:0	DO		7102539 (Z76195) A071862	BRWN FSND LOOS 0020 GREY FSND SILT 0030 GREY CLAY SILT SOFT 0050 GREY CLAY SILT SOFT 0085 GREY FSND CLAY LYRD 0105 GREY FSND LOOS 0121 BRWN
TOSORONTIO TOWNSHIP 03 019	17 581914 4898222 W	2005/05 7088	6.26	FR 0007 FR 0136 FR 0109	25/70/10/1:5	DO	0140 3	5739749 (Z25974) A025507	SAND 0017 GREY CLAY SILT 0035 GREY SILT CLAY SAND 0088 GREY CLAY 0095 GREY SILT SAND 0102 GREY SILT CLYY 0109 GREY SILT SNDY 0131 GREY CLAY SNDY 0136 BRWN SAND 0143

Township Con Lot	UTM	Date Centr	Casing Dia	Water	Pump Test	Well Use	Screen Depth	Well	Formation
TOSORONTIO TOWNSHIP 03 019	17 581866 4898224 W	2005/04 7088	6.26	FR 0010 FR 0111 FR 0138	17/63/10/1:1 2	DO	0139 3	5739684 (Z25962) A016524	BRWN SAND 0018 GREY SILT 0038 GREY CLAY SILT 0088 GREY SILT SAND 0103 GREY SILT CLAY SAND 0108 BRWN SAND SILT 0129 GREY CLAY SAND 0134 GREY SAND SILT 0138 BRWN SAND 0142
TOSORONTIO TOWNSHIP 03 019	17 581354 4897957 W	2005/10 7088	6.26	FR 0006 FR 0125	8/52/6/1:1	DO	0127 3	5740384 (Z33770) A025519	BRWN SAND 0017 GREY SILT SNDY 0037 GREY SAND SLTY 0044 GREY SILT SAND CLAY 0073 GREY CLAY 0094 GREY SILT CLYY SAND 0107 GREY SAND CLYY 0125 GREY SAND 0130
TOSORONTIO TOWNSHIP 03 019	17 581953 4898275 W	2005/04 7088	6.26	FR 0006 FR 0084 FR 0116	19/37/10/1:0	DO	0123 3	5739683 (Z25963) A016525	BRWN SAND 0006 GREY SAND 0027 GREY SILT SAND 0035 GREY CLAY SILT SAND 0074 GREY SAND SILT 0084 BRWN SAND 0093 GREY SAND SILT 0116 BRWN SAND 0127
TOSORONTIO TOWNSHIP 03 019	17 582189 4898129 W	2005/04 7088	6.26	FR 0010 FR 0292 FR 0109	19/40/10/1:	DO	0110 3	5739748 (Z25960) A016527	YLLW SAND 0016 GREY SAND 0036 GREY CLAY SLTY 0062 GREY SILT 0089 GREY FSND 0096 GREY SLTY SNDY 0109 BRWN SAND 0113
TOSORONTIO TOWNSHIP 03 019	17 582018 4898276 W	2005/04 7088	6.26	FR 0008	18/21/10/1:0	DO	0122 3	5739682 (Z25964) A016526	BRWN SAND 0008 GREY SAND 0016 GREY SILT SAND CLAY 0023 GREY CLAY SILT 0054 GREY SILT SAND 0102 GREY CLAY SILT 0108 GREY SILT CLAY SAND 0112 GREY

Township Con Lot	UTM	Date Centr	Casing Dia	Water	Pump Test	Well Use	Screen Depth	Well	Formation
TOSORONTIO TOWNSHIP 03 019	17 581325 4897960 W	2006/07 7088	6.26	0007 0129	9/53/5/1:21	DO	0129 3	5741080 (Z41701) A031193	BRWN SAND SILT 0015 GREY SAND SLTY 0045 GREY SILT CLAY 0078 GREY CLAY 0097 GREY SILT CLAY SAND 0106 GREY SAND CLY 0129 GREY SAND 0132
TOSORONTIO TOWNSHIP 03 019	17 582056 4898285 W	2005/09 7088	6.26	FR 0010 0082 0123	25/40/12/1:0	DO	0123 3	5740393 (Z33763) A025515	BRWN SAND 0019 GREY SILT CLYY 0034 GREY CLAY SLTY 0069 GREY SILT SNDY 0081 BRWN SAND 0092 GREY CLAY SLTY SAND 0116 GREY SAND SLTY 0123 GREY SAND 0126
TOSORONTIO TOWNSHIP 03 019	17 581668 4898044 W	2005/04 7088	6.26	FR 0007 0132	14/66/7/1:0	DO	0132 4	5739686 (Z25961) A016523	BRWN SAND SILT 0018 GREY CLAY SILT 0078 GREY SILT CLAY 0083 GREY SILT 0101 GREY SAND SILT 0123 GREY CLAY SAND 0131 GREY SAND 0136
TOSORONTIO TOWNSHIP 03 019	17 581286 4898119 W	2008/07 4645	6.25	FR 0120	19/65/5/2:	DO	0116 4	7111941 (Z82154) A071366	BLCK LOAM SOFT 0001 BRWN SAND CLAY HARD 0008 BRWN SAND SILT SOFT 0014 BRWN SAND SILT LYRD 0115 BRWN SAND GRVL LOOS 0121
TOSORONTIO TOWNSHIP 03 019	17 582249 4898255 W	2006/04 7088	6.26	FR 0007 0080 0118	16/55/10/1:3 7	DO	0120 3	5740925 (Z33778) A031187	BRWN SAND 0013 GREY SAND 0019 GREY SAND 0051 GREY CLAY 0071 GREY SILT SAND 0080 GREY SAND SILT 0084 GREY CLAY SILT 0111 GREY SAND SILT 0118
TOSORONTIO TOWNSHIP 03 019	17 581752 4898089 W	2005/07 7088	6.26	FR 0007 0040	25/48/10/1:1	DO	0135 3	5739951 (Z33761) A025513	BRWN SAND SILT 0025 GREY SILT SNDY 0043 GREY CLAY 0048 GREY SILT SAND 0054 GREY CLAY SAND 0098 GREY SILT SNDY 0105 GREY SAND SLTY CLAY 0117 GREY FSND SILT 0122 GREY SAND 0140

Township Con Lot	UTM	Date Centr	Casing Dia	Water	Pump Test	Well Use	Screen Depth	Well	Formation
TOSORONTIO TOWNSHIP 03 019	17 581452 4897995 W	2006/07 7088	6.26	0007 0089 0170	15/73/5/1:10	DO	0171 3	5740994 (Z41700) A031194	BRWN SAND SILT 0025 GREY SILT SNDY 0034 GREY CLAY SLTY 0089 GREY SILT SNDY 0117 GREY CLAY SAND 0121 BRWN SAND SLTY 0124 GREY SILT SNDY GRVL 0170 GREY SAND 0174
TOSORONTIO TOWNSHIP 03 019	17 581486 4898003 W	2006/07 7088	6.26	0007 0084 FR 0119	14/62/5/1:17	DO	0119 3	5740993 (Z41713) A031195	BRWN SAND SILT 0011 GREY SAND SILT 0023 GREY SILT SAND CLAY 0033 GREY CLAY CLAY SNDY 0039 GREY SILT SNDY SLTY 0049 GREY CLAY SNDY 0079 GREY SAND SLTY SAND 0089 GREY CLAY SLTY
TOSORONTIO TOWNSHIP 03 019	17 581559 4898025 W	2005/05 7088	6.26	FR 0004 FR 0038	13/55/5/1:4	DO	0125 3	5739751 (Z25975) A025504	BRWN SAND 0019 GREY CLAY SLTY 0045 GREY SILT SAND CLAY 0056 GREY CLAY SLTY 0077 GREY SILT 0088 GREY CLAY SLTY 0106 GREY SILT SNDY 0117 GREY SILT CLAY SAND 0125 BRWN SAND 0128
TOSORONTIO TOWNSHIP 03 019	17 581831 4898073 L	1987/07 4919	30	UK 0010	10/26//:30	DO		5722417 (05081)	BRWN LOAM HARD 0001 BRWN SAND LOOS 0028
TOSORONTIO TOWNSHIP 03 019	17 581831 4898073 L	1987/07 4919	30	UK 0010	10/20//1:0	DO		5722415 (05080)	BRWN SAND PCKD 0028

Township Con Lot	UTM	Date Centr	Casing Dia	Water	Pump Test	Well Use	Screen Depth	Well	Formation
TOSORONTIO TOWNSHIP 03 020	17 581718 4898680 L	1985/08 4919	30	UK 0010	10/20//:30	DO		5720643 ()	BRWN LOAM HARD 0001 BRWN SAND LOOS 0020 GREY CLAY PCKD 0024
TOSORONTIO TOWNSHIP CON 02 019	17 581183 4897933 W	2002/09 7088	6	UK 0010 FR 0118	11/105/13/1: 0	DO	0119 4	5737261 (252305)	BRWN SAND SLTY 0010 GREY SAND SLTY 0026 GREY CLAY SLTY 0038 GREY SILT FSND CLAY 0074 GREY SILT SNDY GRVL
TOSORONTIO TOWNSHIP CON 02 020	17 581114 4898473 W	1974/08 1830	30 24	FR 0018	13/15//1:0	DO		5711528 ()	LOAM SNDY DNSE 0002 BRWN CLAY SNDY PCKD 0013 BRWN FSND LOOS 0018 GREY CLAY PCKD 0029
TOSORONTIO TOWNSHIP CON 03 017	17 581852 4898753 W	1987/12 1413	6	FR 0135	9/120/5/5:40	DO	0131 4	5722862 (24815)	BRWN SAND LOOS 0017 GREY CLAY SNDY 0115 GREY CLAY DNSE 0128 BRWN GRVL SAND LOOS 0136 GREY CLAY SLTY 0148 BRWN SAND PCKD 0156 GREY CLAY DNSE 0164 GREY HPAN HARD 0180
TOSORONTIO TOWNSHIP CON 03 018	17 581826 4897636 W	2002/03 7088	6	UK 0012 UK 0110 FR 0202	12/93/9/7:0	DO		5736747 (230315)	YLLW SAND 0012 GREY SAND 0021 GREY CLAY SNDY 0035 GREY SILT SNDY 0049 GREY SILT CLYY 0082 GREY SAND SILT
TOSORONTIO TOWNSHIP CON 03 018	17 582072 4897646 W	2001/08 7088	6	UK 0017 UK 0086 FR 0201	14/155/13/2: 0	DO	0201 5	5736467 (230302)	BRWN SAND 0017 GREY CLAY SLTY 0043 GREY SAND 0086 BRWN SAND 0104 BRWN SAND SLTY 0118 GREY SILT SNDY 0159 GREY SAND SILT 0164 GREY SAND SLTY
TOSORONTIO TOWNSHIP CON 03 018	17 582172 4897803 W	2003/03 7088	6	FR 0016 FR 0077 FR 0116	13/43/25/1:0	DO	0118 5	5737650 (246071)	YLLW SAND 0016 GREY SAND 0035 GREY SAND CLYY 0043 GREY CLAY SNDY 0059 GREY CLAY SILT 0077 GREY SAND 0079 GREY CLAY 0090 GREY SILT SNDY 0096 GREY FSND SLTY 0116 BRWN SAND 0123

Township Con Lot	UTM	Date Centr	Casing Dia	Water	Pump Test	Well Use	Screen Depth	Well	Formation
TOSORONTIO TOWNSHIP CON 03 019	17 581384 4897973 W	2009/11 7088	6.25	FR 0152	7/21/10/1:0	DO	0152 3	7137336 (Z102991) A089470	BRWN SAND SILT 0018 GREY SILT SAND 0042 GREY CLAY SILT 0078 GREY SILT SAND 0113 GREY CLAY SAND 0122 GREY SILT SAND 0131 GREY SAND SILT CLAY 0152 GREY SAND 0155
TOSORONTIO TOWNSHIP CON 03 019	17 582064 4898046 W	2000/02 2576	6	FR 0196	22/154/4/6:	DO	0191 3	5734946 (214139)	LOAM 0001 BRWN SAND 0010 GREY SAND 0033 GREY CLAY SLTY 0099 GREY SILT 0116 GREY SAND GRVL WBRG 0131 GREY CLAY SLTY 0175 GREY SILT GRVL WBRG 0196
TOSORONTIO TOWNSHIP CON 03 019	17 581828 4898073 L	2001/07 7088	6	FR 0087	7/64/12/1:0	DO	0087 3	5736241 (230297)	BLCK LOAM SAND FILL 0003 BRWN SAND SLTY 0013 GREY CLAY SLTY STNS 0026 GREY FSND SLTY 0067 GREY FSND SILT 0078 GREY FSND SILT CLAY 0087 GREY FSND 0090 GREY SAND SILT CLAY 0092
TOSORONTIO TOWNSHIP CON 03 019	17 581795 4898020 W	2000/02 1663	6	FR 0199	14/21/5/6:	DO IR	0199 7	5735844 (213478)	BRWN PEAT 0004 GREY MSND FSND LOOS 0018 BLUE CLAY SILT SOFT 0093 BRWN FSND 0124 BRWN MSND 0149 BRWN MSND 0154 BLUE CLAY GRVL SAND 0157 BRWN MSND SILT 0185 BLUE CLAY GRVL 0199 GREY GRVL SAND 0218

Township Con Lot	UTM	Date Centr	Casing Dia	Water	Pump Test	Well Use	Screen Depth	Well	Formation
TOSORONTIO TOWNSHIP CON 03 019	17 581303 4897994 W	2001/07 7088	6	FR 0126	3/71/9/1:45	DO	0126 4	5736243 (230298)	BRWN SAND SLTY 0010 GREY SAND SLTY 0020 GREY CLAY 0025 GREY CLAY SLTY 0034 GREY SILT FSND 0044 GREY CLAY SLTY SAND 0087 GREY GRVL CLAY 0125 GREY SAND 0130 GREY SILT 0132
TOSORONTIO TOWNSHIP CON 03 019	17 582130 4898004 W	2003/02 7088	6 6	FR 0013 FR 0083 FR 0132 FR 0232	15/121/15/1: 0	DO		5737651 (252316)	BRWN SAND 0013 GREY SAND 0022 GREY SAND SLTY 0035 GREY SAND CLYY 0064 GREY CLAY SAND GRVL 0083 GREY SAND SILT 0091 GREY SAND SLTY 0132 BRWN SAND 0145 GREY SAND SLTY 0167 GREY GRVL SLTY SNDY 0226 BLUE LMSN 0234
TOSORONTIO TOWNSHIP CON 03 019	17 582120 4897956 W	2003/03 7088	6	FR 0018	18/38/25/1:0	DO	0131 4	5737800 (246070)	YLLW SAND SILT 0016 GREY SAND SILT 0041 GREY CLAY SILT 0076 GREY SILT CLAY 0097 GREY CLAY SLTY 0099 GREY SILT SNDY 0112 GREY FSND SILT 0117 GREY SILT FSND 0121 BRWN SAND 0135
TOSORONTIO TOWNSHIP CON 03 019	17 581831 4898073 L	1990/06 4919	30	UK 0012	12/22/5/1:	DO		5727377 (62591)	BRWN SAND PCKD 0028

Township Con Lot	UTM	Date Centr	Casing Dia	Water	Pump Test	Well Use	Screen Depth	Well	Formation
TOSORONTIO TOWNSHIP CON 03 019	17 581831 4898073 L	1995/09 4645	6	FR 0057	4/40/25/1:0	DO	0053 4	5731988 (163415)	BRWN SAND SILT LOOS 0002 BLCK SAND LOOS 0012 BLCK CLAY SAND SOFT 0022 GREY CLAY SILT LYRD 0045 BLCK SAND LOOS 0057 GREY CLAY SILT DNSE 0062 GREY CLAY SOFT 0080
TOSORONTIO TOWNSHIP CON 03 019	17 581831 4898073 L	1996/09 6915	6	FR 0103	70/85/12/3:0	DO	0097 4	5732512 (163211)	BRWN SAND SILT LOAM 0001 BRWN SAND SILT STNS 0028 BLUE CLAY SAND SOFT 0055 BLUE SILT SAND MSND 0080 BRWN SAND SILT STNS 0088 BRWN FSND SILT SAND 0105
TOSORONTIO TOWNSHIP CON 03 019	17 581690 4898069 W	2005/10 7088	6.26	FR 0013 FR 0112 FR 0130	18/48/5/1:19	DO	0134 3	5740624 (Z33771) A031184	BRWN SAND 0017 GREY SAND SLTY 0021 GREY CLAY SLTY 0076 GREY CLAY SILT 0082 GREY SILT SAND 0103 GREY SAND SILT 0118 GREY SILT 0124 GREY CLAY SLTY
TOSORONTIO TOWNSHIP CON 03 019	17 582273 4898172 W	2004/09 7088	6.26	FR 0160	12/29/10/1:2 7	DO	0161 4	5739289 (Z16615) A000728	BRWN SAND 0012 GREY SAND 0023 GREY CLAY SLTY 0053 GREY SILT 0065 GREY SILT SNDY SLTY 0081 BRWN SAND 0085 GREY SILT SNDY SLTY 0125 GREY SAND SLTY CLAY 0160 GREY SAND GRVL 0165
TOSORONTIO TOWNSHIP CON 03 019	17 582253 4898210 W	2004/07 7088	6.26	0020 0078 0116	22/39/10/1:5	DO	0120 3	5738956 (Z16603) A016513	BRWN SAND 0012 GREY SAND 0020 GREY SAND SLTY CLAY 0049 GREY CLAY SILT 0073 GREY SILT SNDY 0078 GREY SAND SILT 0084 GREY CLAY SLTY 0098 GREY SILT SNDY 0116 BRWN SAND 0123

Township Con Lot	UTM	Date Centr	Casing Dia	Water	Pump Test	Well Use	Screen Depth	Well	Formation
TOSORONTIO TOWNSHIP CON 03 019	17 582259 4898072 W	2004/08 7088	6.26	0006 0082 0123	19/59/10/1:2 0	DO	0125 3	5739106 (Z16607) A016514	BRWN SAND 0013 GREY SAND 0028 GREY CLAY SLTY SAND 0040 GREY CLAY 0063 GREY SILT SNDY 0073 GREY SAND SLTY 0123 BRWN SAND 0128
TOSORONTIO TOWNSHIP CON 03 019	17 582173 4898324 W	2004/09 7088	6.26	FR 0012 FR 0090 FR 0128	24/53/10/1:2	DO	0131 3	5739286 (Z16612) A016520	BRWN SAND 0012 GREY SAND 0020 GREY SILT SAND CLAY 0034 GREY CLAY SLTY 0058 GREY SILT CLAY 0078 GREY SILT SNDY 0105 GREY SILT CLYY SNDY 0112 GREY SILT FSND 0128 GREY SAND 0134
TOSORONTIO TOWNSHIP CON 03 020	17 581270 4898270 W	1990/10 1583	6 5	FR 0172	30//8/1:0	DO	0169 3	5727430 (90390)	SAND 0014 BRWN CLAY 0020 FSND 0044 SILT CLAY 0080 CLAY GRVL 0145 CLAY 0168 CSND 0172 CLAY 0185
TOSORONTIO TOWNSHIP CON 03 020	17 581718 4898680 L	1991/05 4778	6	FR 0116	22/95/5/3:0	DO	0117 5	5728319 (107549)	BRWN SAND 0014 BLUE CLAY SOFT 0068 BLUE CLAY SILT 0116 BRWN FSND 0122
TOSORONTIO TOWNSHIP CON 03 020	17 581981 4898564 W	1991/05 4778	6	FR 0075	23/50/12/1:0	DO	0077 5	5728320 (107548)	BRWN SAND 0014 BLUE CLAY SOFT 0057 BLUE CLAY SAND LYRD 0075 FSND 0082

Township Con Lot	UTM	Date Centr	Casing Dia	Water	Pump Test	Well Use	Screen Depth	Well	Formation
TOSORONTIO TOWNSHIP CON 03 020	17 581999 4898594 W	4778	6	FR 0066	23/50/10/2:0	DO	0077 6	5728763 (107555)	BRWN SAND 0018 BLUE CLAY SAND 0052 BLUE CLAY SOFT 0066 BRWN SAND CLAY LYRD 0083
TOSORONTIO TOWNSHIP CON 03 020	17 581887 4898539 W	1992/01 4778	6	FR 0113	23/50/20/2:0	DO	0115 5	5728871 (107572)	BRWN LOAM 0002 BRWN SAND 0014 BLUE CLAY SOFT 0052 BLUE SILT CLAY 0067 BLUE CLAY SILT SAND 0087 BLUE CLAY SOFT 0102 BLUE CLAY SAND 0113 BRWN FSND CLN 0120
TOSORONTIO TOWNSHIP CON 03 020	17 581715 4898377 W	2004/06 7088	6.26	FR 0116	23/27/31/1:5 0	CO	0135 5 0141 5	5738906 (Z00828) A000725	BRWN SAND 0006 BRWN CLAY SLTY 0011 GREY CLAY SLTY SAND 0018 GREY SILT CLYY SAND 0047 GREY SILT SNDY 0065 GREY SILT CLYY 0095 GREY SILT SNDY 0116 BRWN SAND 0146
TOSORONTIO TOWNSHIP CON 03 020	17 581718 4898680 L	1990/05 5206			37/46/10/4:0	DO	0123 3	5726684 (70641)	BRWN SAND 0037 BRWN CLAY SNDY 0118 CLAY SAND 0126
TOSORONTIO TOWNSHIP CON 03 020	17 581204 4898487 W	1989/01 4919	30	UK 0020	15/26/5/1:0	DO		5724928 (47149)	BRWN SAND LOOS 0020 GREY CLAY HARD 0030

Township Con Lot	UTM	Date Centr	Casing Dia	Water	Pump Test	Well Use	Screen Depth	Well	Formation
TOSORONTIO TOWNSHIP CON 03 020	17 581718 4898680 L	4778	6	FR 0116	27/35/12/1:0	DO	0119 6	5724841 (55218)	BRWN SAND 0018 BLUE CLAY SOFT 0036 BLUE CLAY SAND SILT 0072 BLUE CLAY SOFT 0090 BLUE CLAY SILT SOFT 0110 FSND CLAY 0116 MSND CLN WBRG 0125
TOSORONTIO TOWNSHIP CON 03 020	17 581877 4898543 W	4778	6	FR 0102	27/80/12/1:0	DO	0107 6	5724844 (55215)	LOAM 0003 BRWN SAND 0021 BLUE CLAY SOFT 0035 BLUE CLAY SILT 0063 BLUE CLAY SOFT 0092 BLUE SILT CLAY HARD 0100 BLUE SILT CLAY SOFT 0102 FSND WBRG 0113
TOSORONTIO TOWNSHIP CON 03 020	17 581809 4898625 W	1989/03 4778	6	FR 0118	24/90/10/1:0	DO	0120 5	5724843 (55214)	LOAM 0002 BRWN SAND 0015 BRWN CLAY SAND 0022 BLUE CLAY SAND 0070 BLUE CLAY SOFT 0111 FSND CMTD 0118 FSND WBRG 0125
TOSORONTIO TOWNSHIP CON 03 020	17 581829 4898583 W	1989/03 4778	6	FR 0118	24/37/12/1:0	DO	0118 5	5724835 (55213)	LOAM 0002 BRWN SAND 0015 BRWN CLAY SAND 0022 BLUE CLAY SAND 0070 BLUE CLAY SOFT 0111 FSND CMTD 0118
TOSORONTIO TOWNSHIP CON 04 020	17 581910 4898599 W	1989/10 4778	6	FR 0132	24/70/10/2:0	DO	0132 5	5726225 (55238)	BRWN SAND 0018 BLUE CLAY 0032 BLUE CLAY SILT 0090 BLUE SILT 0118 BLUE CLAY CMTD SAND 0132 BRWN SAND 0137

UTM: UTM in Zone, Easting, Northing and Datum is NAD83; L: UTM estimated from Centroid of Lot; W: UTM not from Lot Centroid
 DATE CNTR: Date Work Completed and Well Contractor Licence Number
 CASING DIA: Casing diameter in inches
 WATER: Unit of Depth in Feet. See Table 4 for meaning of code.
 PUMP TEST: Static Water Level in Feet / Water Level After Pumping in Feet / Pump Test Rate in GPM / Pump Test Duration in Hr : Min
 WELL USE: See Table 3 for Meaning of Code
 SCREEN: Screen Depth and Length in feet
 WELL: WEL (AUDIT #) Well Tag. A: Abandonment; P: Partial Data Entry Only
 FORMATION: See Table 1 and 2 for Meaning of Code

BLDR BOULDERS	FCRD FRACTURED	IRFM IRON FORMATION	PORS POROUS	SOFT SOFT
BSLT BASALT	FGRD FINE-GRAINED	LIMY LIMY	PRDG PREVIOUSLY DUG	SPST SOAPSTONE
CGRD COARSE-GRAINED	FGVL FINE GRAVEL	LMSN LIMESTONE	PRDR PREV. DRILLED	STKY STICKY
CGVL COARSE GRAVEL	FILL FILL	LOAM TOPSOIL	QRTZ QUARTZITE	STNS STONES
CHRT CHERT	FLDS FELDSPAR	LOOS LOOSE	QSND QUICKSAND	STNY STONEY
CLAY CLAY	FLNT FLINT	LTCL LIGHT-COLOURED	QTZ QUARTZ	THIK THICK
CLN CLEAN	FOSS FOSILIFEROUS	LYRD LAYERED	ROCK ROCK	THIN THIN
CLYY CLAYEY	FSND FINE SAND	MARL MARL	SAND SAND	TILL TILL
CMTD CEMENTED	GNIS GNEISS	MGRD MEDIUM-GRAINED	SHLE SHALE	UNKN UNKNOWN TYPE
CONG CONGLOMERATE	GRNT GRANITE	MGVL MEDIUM GRAVEL	SHLY SHALY	VERY VERY
CRYS CRYSTALLINE	GRSN GREENSTONE	MRBL MARBLE	SHRP SHARP	WBRG WATER-BEARING
CSND COARSE SAND	GRVL GRAVEL	MSND MEDIUM SAND	SHST SCHIST	WDFR WOOD FRAGMENTS
DKCL DARK-COLOURED	GRWK GREYWACKE	MUCK MUCK	SILT SILT	WTHD WEATHERED
DLMT DOLOMITE	GVLY GRAVELLY	OBDN OVERBURDEN	SLTE SLATE	
DNSE DENSE	GYPS GYPSUM	PCKD PACKED	SLTY SILTY	
DRTY DIRTY	HARD HARD	PEAT PEAT	SNDS SANDSTONE	
DRY DRY	HPAN HARDPAN	PGVL PEA GRAVEL	SNDY SANDYOAPSTONE	

WHIT WHITE
GREY GREY
BLUE BLUE
GREN GREEN
YLLW YELLOW
BRWN BROWN
RED RED
BLCK BLACK
BLGY BLUE-GREY

DO Domestic	OT Other
ST Livestock	TH Test Hole
IR Irrigation	DE Dewatering
IN Industrial	MO Monitoring
CO Commercial	MT Monitoring TestHole
MN Municipal	
PS Public	
AC Cooling And A/C	
NU Not Used	

FR Fresh	GS Gas
SA Salty	IR Iron
SU Sulphur	
MN Mineral	
UK Unknown	

A000725
A 000725

Instructions for Completing Form

- For use in the **Province of Ontario** only. This document is a permanent **legal** document. Please retain for future reference.
- All Sections **must** be completed in full to avoid delays in processing. Further instructions and explanations are available on the back of this form.
- Questions regarding completing this application can be directed to the Water Well Management Coordinator at 416-235-6203.
- **All metre measurements shall be reported to 1/10th of a metre.**
- Please print clearly in blue or black ink only.

Well Owner's Information and Location of Well Information				Ministry Use Only			
MUN 57015		CON CON		LOT 03		LOT 19	
First Name SILVER BROOKE GOLF CLUB		Last Name		Mailing Address (Street Number/Name, RR, Lot, Concession)			
County/District/Municipality		Township/City/Town/Village		Province Ontario		Postal Code	
Telephone Number (include area code)		Address of Well Location (County/District/Municipality) SIMCOE COUNTY		Township TOSORONTIO TWP		Lot 19 Concession CON 3	
RR#/Street Number/Name		City/Town/Village		Site/Compartment/Block/Tract etc.			
GPS Reading	NAD 83	Zone 17	Easting 581715	Northing 4898377	Unit Make/Model GARMIN ETREX	Mode of Operation: <input checked="" type="checkbox"/> Undifferentiated <input type="checkbox"/> Averaged <input type="checkbox"/> Differentiated, specify	

Log of Overburden and Bedrock Materials (see instructions)

General Colour	Most common material	Other Materials	General Description	DEPTH (FT)	Depth From	Metres To
BROWN	SAND			0	6	1.8
BROWN	CLAY	SILTY		6	11	3.4
GREY	CLAY	SILTY SAND LAYERS		11	18	5.5
GREY	SILT	CLAYEY SAND		18	47	14.3
GREY	SILT	CLAYEY SANDY		47	65	19.8
GREY	SILT	CLAYEY		65	95	29.0
GREY	SILT	SANDY		95	116	35.4
BROWN	SAND			116	146	44.5

Hole Diameter			Construction Record				Test of Well Yield					
Depth From	Metres To	Diameter Centimetres	Inside diam centimetres	Material	Wall thickness centimetres	Depth From	Metres To	Pumping test method	Draw Down Time min	Water Level Metres	Recovery Time min	Water Level Metres
				<input checked="" type="checkbox"/> Steel <input type="checkbox"/> Fibreglass <input type="checkbox"/> Plastic <input type="checkbox"/> Concrete <input type="checkbox"/> Galvanized	0.48	0.72	41.1	Pump intake set at - (metres) 30	1	7.0	1	7.3
Water Record			Casing				Test of Well Yield					
Water found at Metres	Kind of Water		Screen				Test of Well Yield					
35.4 m	<input checked="" type="checkbox"/> Fresh <input type="checkbox"/> Sulphur <input type="checkbox"/> Gas <input type="checkbox"/> Salty <input type="checkbox"/> Minerals <input type="checkbox"/> Other:		Outside diam 14.6				Test of Well Yield					
			<input type="checkbox"/> Steel <input type="checkbox"/> Fibreglass <input checked="" type="checkbox"/> Stainless Steel <input type="checkbox"/> Concrete <input type="checkbox"/> Galvanized				Test of Well Yield					
			Slot No. 18				Test of Well Yield					
			18				Test of Well Yield					
			41.3				Test of Well Yield					
			43.0				Test of Well Yield					
			44.5				Test of Well Yield					
After test of well yield, water was <input checked="" type="checkbox"/> Clear and sediment free			No Casing or Screen				Test of Well Yield					
<input type="checkbox"/> Other, specify			<input type="checkbox"/> Open hole				Test of Well Yield					
Chlorinated <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No							Test of Well Yield					

Plugging and Sealing Record			<input checked="" type="checkbox"/> Annular space	<input type="checkbox"/> Abandonment
Depth set at - Metres From	To	Material and type (bentonite slurry, neat cement slurry) etc.	Volume Placed (cubic metres)	
0	6.1	BENTONITE SLURRY	0.2	

Method of Construction			
<input checked="" type="checkbox"/> Cable Tool	<input type="checkbox"/> Rotary (air)	<input type="checkbox"/> Diamond	<input type="checkbox"/> Digging
<input type="checkbox"/> Rotary (conventional)	<input type="checkbox"/> Air percussion	<input type="checkbox"/> Jetting	<input type="checkbox"/> Other
<input type="checkbox"/> Rotary (reverse)	<input type="checkbox"/> Boring	<input type="checkbox"/> Driving	
Water Use			
<input type="checkbox"/> Domestic	<input type="checkbox"/> Industrial	<input type="checkbox"/> Public Supply	<input type="checkbox"/> Other
<input type="checkbox"/> Stock	<input checked="" type="checkbox"/> Commercial	<input type="checkbox"/> Not used	
<input type="checkbox"/> Irrigation	<input type="checkbox"/> Municipal	<input type="checkbox"/> Cooling & air conditioning	
Final Status of Well			
<input checked="" type="checkbox"/> Water Supply	<input type="checkbox"/> Recharge well	<input type="checkbox"/> Unfinished	<input type="checkbox"/> Abandoned, (Other)
<input type="checkbox"/> Observation well	<input type="checkbox"/> Abandoned, insufficient supply	<input type="checkbox"/> Dewatering	
<input type="checkbox"/> Test Hole	<input type="checkbox"/> Abandoned, poor quality	<input type="checkbox"/> Replacement well	

Well Contractor/Technician Information	
Name of Well Contractor COUNTRY WATER SYSTEMS	Well Contractor's Licence No. 7088
Business Address (street name, number, city etc.) 6995 SIMCOE RD 56, UTOPIA (877) 333-9355.	
Name of Well Technician (last name, first name) SCOTT PETER	Well Technician's Licence No. T-1667
Signature of Technician/Contractor <i>[Signature]</i>	Date Submitted YYY Y MM DD

Location of Well	
In diagram below show distances of well from road, lot line, and building. Indicate north by arrow.	
Audit No. Z 00828	Date Well Completed YYY Y MM DD 2004 06 25
Was the well owner's information package delivered? <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No	Date Delivered YYY Y MM DD 2004 06 30

Ministry Use Only	
Data Source	Contractor 7088
Date Received YYY Y MM DD JUL 13 2004	Date of Inspection YYY Y MM DD
Remarks	Well Record Number 5738906

Appendix C: Test Well Construction Records

Tag#: A366563

Measurements recorded in: Metric Imperial

Page 0 of 1

Well Owner's information

First Name: 2834556 Last Name/Organization: ONTARIO INC E-mail Address: Well Constructed by Well Owner
 Mailing Address (Street Number/Name): 45 CINDY LANE Municipality: TORONTO Province: Ontario Postal Code: Telephone No. (inc. area code): 647 3846795

Well Location

Address of Well Location (Street Number/Name): 45 CINDY LANE Township: TORONTO Lot: 19 Concession: 3
 County/District/Municipality: SIMCOE COUNTY City/Town/Village: Province: Ontario Postal Code:
 UTM Coordinates Zone: Easting: Northing: Municipal Plan and Sublot Number: Other: T2001

Overburden and Bedrock Materials/Abandonment Sealing Record (see instructions on the back of this form)

General Colour	Most Common Material	Other Materials	General Description	Depth (m/ft) From	Depth (m/ft) To
	TOP SOIL			0	15
BROWN	SAND			1	15
GREY	SAND			15	21
GREY	CLAY			21	27
GREY	SILTY CLAY			27	96
GREY	SAND	SILT	WMT	96	113
BROWN	SAND		WMT, FINE	113	123
BROWN	SAND	GRAVEL	WMT, LOOSE	123	136

Annular Space

Depth Set at (m/ft) From	Depth Set at (m/ft) To	Type of Sealant Used (Material and Type)	Volume Placed (m³/ft³)
0	20	HOLE PLUG	2 BAGS
2	20	GRACK GROUT	50 LMS

Method of Construction: Cable Tool Rotary (Conventional) Rotary (Reverse) Boring Air percussion Other, specify: AIR DRILL

Well Use: Public Commercial Not used Domestic Municipal Dewatering Livestock Test Hole Monitoring Irrigation Cooling & Air Conditioning Industrial Other, specify:

Construction Record - Casing

Inside Diameter (cm/in)	Open Hole OR Material (Galvanized, Fibreglass, Concrete, Plastic, Steel)	Wall Thickness (cm/in)	Depth (m/ft) From	Depth (m/ft) To	Status of Well
6 1/4	STEEL	.188	+2	131	<input checked="" type="checkbox"/> Water Supply <input type="checkbox"/> Replacement Well <input checked="" type="checkbox"/> Test Hole <input type="checkbox"/> Recharge Well <input type="checkbox"/> Dewatering Well <input type="checkbox"/> Observation and/or Monitoring Hole <input type="checkbox"/> Alteration (Construction) <input type="checkbox"/> Abandoned, Insufficient Supply <input type="checkbox"/> Abandoned, Poor Water Quality <input type="checkbox"/> Abandoned, other, specify: <input type="checkbox"/> Other, specify:
	W. PLUG		129	129	
6 1/4	STEEL	.188	129	131	

Construction Record - Screen

Outside Diameter (cm/in)	Material (Plastic, Galvanized, Steel)	Slot No.	Depth (m/ft) From	Depth (m/ft) To
6 1/2	S. STEEL	16	131	135

Water Details

Water found at Depth (m/ft)	Kind of Water: <input checked="" type="checkbox"/> Fresh <input checked="" type="checkbox"/> Untested <input type="checkbox"/> Gas <input type="checkbox"/> Other, specify:	Hole Diameter Depth (m/ft) From	Hole Diameter Depth (m/ft) To	Hole Diameter (cm/in)
131-135		0	20	10 3/8
		20	131	6 3/8

Well Contractor and Well Technician Information

Business Name of Well Contractor: HIGHLAND WATER WELLS Well Contractor's Licence No.: 25716
 Business Address (Street Number/Name): Box 141, Durham Municipality: WEST GORE
 Province: ONT Postal Code: N0G 1R0 Business E-mail Address: highlanddrilling@buts.com

Bus. Telephone No. (inc. area code): 519 369 6363 Name of Well Technician (Last Name, First Name): POPPLETON, NIGEL
 Well Technician's Licence No.: 2130 Signature of Technician and/or Contractor: [Signature] Date Submitted: 20240521

Results of Well Yield Testing

Time (min)	Draw Down		Recovery	
	Water Level (m/ft)	Time (min)	Water Level (m/ft)	Time (min)
After test of well yield, water was: <input checked="" type="checkbox"/> Clear and sand free <input type="checkbox"/> Other, specify:				
If pumping discontinued, give reason: Static Level: 16.7				
1	18.1	1	17	
2	18.1	2	16.9	
3	18.3	3	16.9	
4	18.3	4	16.9	
5	18.3	5	16.9	
10	18.3	10	16.9	
15	18.3	15	16.9	
20	18.4	20	16.8	
25	18.4	25	16.8	
30	18.3	30	16.8	
40	18.4	40	16.8	
50	18.4	50	16.8	
60	18.4	60	16.7	

Pump intake set at (m/ft): 55 FT
 Pumping rate (l/min / GPM): 8 GPM
 Duration of pumping: 6 hrs + min
 Final water level end of pumping (m/ft): 18.6
 If flowing give rate (l/min/GPM):
 Recommended pump depth (m/ft): 5-50 FT
 Recommended pump rate (l/min/GPM): 10-15
 Well production (l/min/GPM): 60+
 Disinfected? Yes No

Map of Well Location

Please provide a map below following instructions on the back.

Comments: FOR 100' ONLY

Well owner's information package delivered	Date Package Delivered	Ministry Use Only
<input checked="" type="checkbox"/> Yes <input type="checkbox"/> No	20240522	Audit No: 2425750
Date Work Completed	20240515	Received

Measurements recorded in: Metric Imperial

Tag#: A366566

Page 0 of 1

Well Owner's Information

First Name: D834556 Last Name/Organization: ONTARIO INC. E-mail Address: _____ Well Constructed by Well Owner
 Mailing Address (Street Number/Name): _____ Municipality: _____ Province: _____ Postal Code: _____ Telephone No. (inc. area code): 647 3846795

Well Location

Address of Well Location (Street Number/Name): LINDY LANE Township: TOSORONTO TWP Lot: 19 Concession: 3
 County/District/Municipality: SIMCOE COUNTY City/Town/Village: _____ Province: Ontario Postal Code: _____
 UTM Coordinates Zone: 18 Easting: 8317581594 Northing: 4898083 Municipal Plan and Sublot Number: _____ Other: TW 02

Overburden and Bedrock Materials/Abandonment Sealing Record (see instructions on the back of this form)

General Colour	Most Common Material	Other Materials	General Description	Depth (m/ft)	
				From	To
	TOP SOIL			0	1
BROWN	SAND			1	12
GREY	SAND			12	22
GREY	CLAY	GRANITE		22	76
GREY	CLAY	SILT/SAND LAYERS		76	96
GREY	SILT	SAND	BROWN LAYERS	96	124
GREY	CLAY			124	128
BROWN	SAND		WET	128	129
GREY	CLAY	STONES	HARD	129	136

Annular Space

Depth Set at (m/ft)	Type of Sealant Used	Volume Placed
From	(Material and Type)	(m ³ /ft ³)
0 2	HOLE PLUG	2 BAGS
2 20	GROUT	50 BAGS

Method of Construction: Cable Tool Diamond Rotary (Conventional) Jetting Rotary (Reverse) Boring Air percussion Other, specify: Aug 12

Well Use: Public Commercial Not used Domestic Municipal Dewatering Livestock Test Hole Monitoring Irrigation Cooling & Air Conditioning Industrial Other, specify: _____

Construction Record - Casing

Inside Diameter (cm/in)	Open Hole OR Material (Galvanized, Fibreglass, Concrete, Plastic, Steel)	Wall Thickness (cm/in)	Depth (m/ft)		Status of Well
			From	To	
6 1/4	STEEL	.188	+2	120	<input checked="" type="checkbox"/> Water Supply <input type="checkbox"/> Replacement Well <input checked="" type="checkbox"/> Test Hole <input type="checkbox"/> Recharge Well <input type="checkbox"/> Dewatering Well <input type="checkbox"/> Observation and/or Monitoring Hole <input type="checkbox"/> Alteration (Construction) <input type="checkbox"/> Abandoned, Insufficient Supply <input type="checkbox"/> Abandoned, Poor Water Quality <input type="checkbox"/> Abandoned, other, specify _____ <input type="checkbox"/> Other, specify _____
5 1/2	V. PALCO		118	118	
5 1/4	STEEL		118	120	

Construction Record - Screen

Outside Diameter (cm/in)	Material (Plastic, Galvanized, Steel)	Slot No.	Depth (m/ft)	
			From	To
5 1/2	S. STEEL	12	120	124

Water Details

Water found at Depth (m/ft)	Kind of Water:	Depth (m/ft)	Diameter (cm/in)
120-124	<input checked="" type="checkbox"/> Fresh <input type="checkbox"/> Untested <input type="checkbox"/> Gas <input type="checkbox"/> Other, specify _____	0 20	10 3/8
	<input type="checkbox"/> Fresh <input type="checkbox"/> Untested <input type="checkbox"/> Gas <input type="checkbox"/> Other, specify _____	20 120	6 5/8

Well Contractor and Well Technician Information

Business Name of Well Contractor: HIGHLAND WATER WELLS Well Contractor's Licence No.: 2576
 Business Address (Street Number/Name): Box 141, Durham Municipality: WEST GUY
 Province: ONT Postal Code: N0G1R0 Business E-mail Address: highlanddrilling@bwts.com

Bus. Telephone No. (inc. area code): 519 369 6363 Name of Well Technician (Last Name, First Name): ROBERT WILSON
 Well Technician's Licence No.: 2130 Signature of Technician and/or Contractor: _____ Date Submitted: 20240521

Results of Well Yield Testing

Time (min)	Water Level (m/ft)	Recovery	
		Time (min)	Water Level (m/ft)
Static Level	15.7		
1	20.1	1	21.9
2	22.6	2	19.8
3	24.1	3	18.6
4	25	4	17.8
5	25.4	5	17.4
10	26.3	10	16.6
15	26.4	15	16.4
20	26.4	20	16.4
25	26.4	25	16.3
30	26.3	30	16.3
40	26.3	40	16.2
50	26.3	50	16.2
60	26.3	60	16

After test of well yield, water was: Clear and sand free Other, specify _____
 If pumping discontinued, give reason: _____
 Pump intake set at (m/ft): 55ft
 Pumping rate (l/min / GPM): 8 GPM
 Duration of pumping: 6 hrs + _____ min
 Final water level end of pumping (m/ft): 26.9
 If flowing give rate (l/min/GPM): _____
 Recommended pump depth (m/ft): 50-60ft
 Recommended pump rate (l/min/GPM): 10 GPM
 Well production (l/min/GPM): 30
 Disinfected? Yes No

Map of Well Location

Please provide a map below following instructions on the back.

AN

LINDY LANE

TW 02

SILVER BROOKE GOLF CLUB

CON 3

Comments: Fee 100.00

Well owner's information package delivered	Date Package Delivered	Ministry Use Only
<input checked="" type="checkbox"/> Yes <input type="checkbox"/> No	<u>20240521</u>	Audit No: <u>2425747</u>
	Date Work Completed: <u>20240516</u>	Received: _____

A366565

Measurements recorded in: Metric Imperial

Well Owner's Information

First Name: 2834556 Last Name/Organization: ONTARIO INC E-mail Address: Well Constructed by Well Owner
 Mailing Address (Street Number/Name): _____ Municipality: _____ Province: _____ Postal Code: _____ Telephone No. (inc. area code): 647 384 6795

Well Location

Address of Well Location (Street Number/Name): 45 CINDY LANE Township: TOSORANTIO Lot: 19 Concession: 3
 County/District/Municipality: SIMCOE COUNTY City/Town/Village: _____ Province: Ontario Postal Code: _____
 UTM Coordinates Zone: NAD 83 Easting: 17589429 Northing: 4898044 Municipal Plan and Sublot Number: _____ Other: T2003

Overburden and Bedrock Materials/Abandonment Sealing Record (see instructions on the back of this form)

General Colour	Most Common Material	Other Materials	General Description	Depth (m/ft) From	Depth (m/ft) To
	TOP SOIL			0	1.5L
BROWN	SAND			1	7
GRAY	SAND			7	13
GRAY	CLAY		SILTY	13	35
GRAY	SAND	BROWN SAND	FINE	35	48
GRAY	CLAY			48	103
GRAY	SAND		FINE	103	118
GRAY	SAND	GRAVEL	COMPACTED	118	136
GRAY	SAND	BROWN SAND	FINE -> MEDIUM WT	136	156

Annular Space			Volume Placed (m³/ft³)
Depth Set at (m/ft) From	Depth Set at (m/ft) To	Type of Sealant Used (Material and Type)	
0	2	HOPE PLUG	2 BAGS
2	20	QUICK GROUT	50 GAL'S.

Method of Construction: Cable Tool Rotary (Conventional) Rotary (Reverse) Boring Air percussion Other, specify: ABE DL

Well Use: Public Domestic Livestock Industrial Commercial Municipal Test Hole Cooling & Air Conditioning Not used Dewatering Monitoring

Construction Record - Casing			Depth (m/ft)		Status of Well
Inside Diameter (cm/in)	Open Hole OR Material (Galvanized, Fibreglass, Concrete, Plastic, Steel)	Wall Thickness (cm/in)	From	To	
6 1/4	STEEL	.188	+2	149	<input checked="" type="checkbox"/> Water Supply
	K PACKER		147	147	<input type="checkbox"/> Replacement Well
5 1/4	STEEL		147	149	<input checked="" type="checkbox"/> Test Hole

Construction Record - Screen			Depth (m/ft)		Status of Well
Outside Diameter (cm/in)	Material (Plastic, Galvanized, Steel)	Slot No.	From	To	
5 1/2	S. STEEL	12	149	153	<input type="checkbox"/> Recharge Well

Water Details		Hole Diameter		
Water found at Depth (m/ft)	Kind of Water: <input type="checkbox"/> Fresh <input checked="" type="checkbox"/> Untested	Depth (m/ft) From	Depth (m/ft) To	Diameter (cm/in)
149-153	<input type="checkbox"/> Gas <input type="checkbox"/> Other, specify _____	0	20	10 5/8
	<input type="checkbox"/> Gas <input type="checkbox"/> Other, specify _____	20	149	6 9/8

Well Contractor and Well Technician Information


Business Name of Well Contractor: HIGHLAND WATER WELLS Well Contractor's Licence No.: 25776
 Business Address (Street Number/Name): Box 141, Oshawa Municipality: WEST GRET
 Province: ONT Postal Code: N0G1L0 Business E-mail Address: highlanddrilling@butts.com
 Bus. Telephone No. (inc. area code): 519 369 6363 Name of Well Technician (Last Name, First Name): POPPARD, NIKE
 Well Technician's Licence No.: 2130 Signature of Technician and/or Contractor: _____ Date Submitted: 20240521

Results of Well Yield Testing			
Time (min)	Water Level (m/ft)	Recovery	
		Time (min)	Water Level (m/ft)
After test of well yield, water was: <input checked="" type="checkbox"/> Clear and sand free <input type="checkbox"/> Other, specify _____			
If pumping discontinued, give reason: Static Level: 10.8			
1	18	1	67.2
2	19.22	2	63.7
3	22.37	3	60.55
4	25.06	4	57.65
5	27.8	5	54.9
10	37.88	10	43.9
15	46.11	15	36.4
20	50	20	31.2
25	54.05	25	27.55
30	56.65	30	25
40	58	40	21.9
50	59.56	50	20.1
60	62.58	60	19.05

Pump intake set at (m/ft): 107.4
 Pumping rate (l/min / GPM): 8
 Duration of pumping: 6 hrs + ___ min
 Final water level end of pumping (m/ft): 73.7
 If flowing give rate (l/min/GPM): _____

Recommended pump depth (m/ft): 100.5L
 Recommended pump rate (l/min/GPM): 8 GPM
 Well production (l/min/GPM): 9 GPM

Disinfected? Yes No




Comments: For 150 mgl


Well owner's information package delivered	Date Package Delivered	Ministry Use Only
<input checked="" type="checkbox"/> Yes	2024 05 22	Audit No. 2425749
<input type="checkbox"/> No	2024 05 15	Received: _____

Appendix D: Pumping Test Results


TW1 - 6-Hour Pumping test



TW2 6-Hr Pumping Test



TW3 - 6-Hour Pumping test



Appendix E: Laboratory Certificates of Analysis

C.O.C.: DW136256

REPORT No: 24-014134 - Rev. 0

Report To:

Tatham Engineering
 115 Sandford Fleming Drive
 Suite 200
 Collingwood, ON L9Y 5A6

CADUCEON Environmental Laboratories

112 Commerce Park Dr Unit L
 Barrie, ON L4N 8W8

Attention: Kimberly Gardner

DATE RECEIVED: 2024-May-16
 DATE REPORTED: 2024-May-23
 SAMPLE MATRIX: Ground Water

CUSTOMER PROJECT: 423499
 P.O. NUMBER:

Analyses	Qty	Site Analyzed	Authorized	Date Analyzed	Lab Method	Reference Method
Anions (Liquid)	4	OTTAWA	PCURIEL	2024-May-22	A-IC-01	SM 4110B
Colour (Liquid)	2	OTTAWA	STAILLON	2024-May-22	A-COL-01	SM 2120C
Cond/pH/Alk Auto (Liquid)	2	OTTAWA	SBOUDREAU	2024-May-22	COND-02/PH-02/A LK-02	SM 2510B/4500H/ 2320B
DOC/DIC (Liquid)	2	OTTAWA	VKASYAN	2024-May-22	C-OC-01	EPA 415.2
E.Coli m-TECH Media (Liquid)	4	BARRIE	IPATEL	2024-May-16	EC-001	MECP E3371
ICP/OES (Liquid)	4	OTTAWA	NHOGAN	2024-May-22	D-ICP-01	SM 3120B
Ammonia (Liquid)	2	KINGSTON	JYEARWOOD	2024-May-21	NH3-001	SM 4500NH3
Total Coliforms (m-Endo Media)	4	BARRIE	IPATEL	2024-May-16	TC-001	SM 9222B
Turbidity (Liquid)	4	OTTAWA	PLUSSIER	2024-May-21	A-TURB-01	SM 2130B

R.L. = Reporting Limit

NC = Not Calculated

Test methods may be modified from specified reference method unless indicated by an *



Michelle Dubien
Data Specialist

CADUCEON Environmental Laboratories Certificate of Analysis

Final Report
REPORT No: 24-014134 - Rev. 0

Parameter	Units	R.L.	Limits	Client I.D.	TW 1 - 1hr	TW 3 - 1hr	TW 1 - 6hr	TW 3 - 6hr	
					Sample I.D.	24-014134-1	24-014134-2	24-014134-3	24-014134-4
					Date Collected	2024-May-15	2024-May-15	2024-May-15	2024-May-15
					DWG	-	-	-	-
Total Coliform	CFU/100mL	1	0	MAC	<2	<2	<2	4	
Background	CFU/100mL	1			<2	42	12	6	
E coli	CFU/100mL	1	0	MAC	0	0	0	0	
Alkalinity(CaCO3) to pH4.5	mg/L	5	500	OG			193	190	
TDS (Calc. from Cond.)	mg/L	3	500	AO			195	190	
Conductivity @25°C	uS/cm	1					379	369	
pH @25°C	pH units	-	8.5	OG			7.98	7.94	
Colour	TCU	2	5	AO			<2	<2	
Turbidity	NTU	0.1	5	AO	31.2	82.7	4.0	10.1	
Chloride	mg/L	0.5	250	AO			0.9	3.3	
Nitrate (N)	mg/L	0.05	10.0	MAC	0.06	0.11	<0.05	<0.05	
Nitrite (N)	mg/L	0.05	1.0	MAC	<0.05	<0.05	<0.05	<0.05	
Ammonia (N)-Total (NH3+NH4)	mg/L	0.05					0.06	0.18	
Dissolved Organic Carbon	mg/L	0.2	5	AO			1.2	<0.2	
Hardness (as CaCO3)	mg/L as CaCO3	0.02	100	OG			194	168	
Calcium	mg/L	0.02					45.9	39.6	
Magnesium	mg/L	0.02					19.2	16.7	
Manganese	mg/L	0.001	0.05	AO			0.024	0.027	
Sodium	mg/L	0.2	200, 20, 20	AO, WL, MAC	5.2	14.5	4.9	13.9	



Michelle Dubien
Data Specialist

The analytical results reported herein refer to the samples as received and relate only to the items tested. Reproduction of this analytical report in full or in part is prohibited without prior consent from Caduceon Environmental Laboratories.

DWG - Drinking Water Guidelines

ODWS - Ontario Drinking Water Standards
 AO - Aesthetic Objectives
 IMAC - Interim Maximum Acceptable Concentration
 MAC - Maximum Acceptable Concentration
 ODWO - D-5-5 Objective
 OG - Operational Guidelines
 WL - Warning Level - Sodium Restricted Diets

Summary of Exceedances		
Aesthetic Objectives		
TW 1 - 1hr	Found Value	Limit
Turbidity	31.2	5
TW 3 - 1hr	Found Value	Limit
Turbidity	82.7	5
TW 3 - 6hr	Found Value	Limit
Turbidity	10.1	5
Maximum Acceptable Concentration		
TW 1 - 1hr	Found Value	Limit
Total Coliform	<2	0
TW 3 - 1hr	Found Value	Limit
Total Coliform	<2	0
TW 1 - 6hr	Found Value	Limit
Total Coliform	<2	0
TW 3 - 6hr	Found Value	Limit
Total Coliform	4	0
Operational Guidelines		
TW 1 - 6hr	Found Value	Limit
Hardness (as CaCO ₃)	194	100
TW 3 - 6hr	Found Value	Limit
Hardness (as CaCO ₃)	168	100



Michelle Dubien
 Data Specialist

C.O.C.: DW112363

REPORT No: 24-014150 - Rev. 0

Report To:

Tatham Engineering
 115 Sandford Fleming Drive
 Suite 200
 Collingwood, ON L9Y 5A6

CADUCEON Environmental Laboratories

112 Commerce Park Dr Unit L
 Barrie, ON L4N 8W8

Attention: Kimberly Gardner

DATE RECEIVED: 2024-May-17
 DATE REPORTED: 2024-May-23
 SAMPLE MATRIX: Ground Water

CUSTOMER PROJECT: 423499
 P.O. NUMBER:

Analyses	Qty	Site Analyzed	Authorized	Date Analyzed	Lab Method	Reference Method
Anions (Liquid)	2	OTTAWA	PCURIEL	2024-May-22	A-IC-01	SM 4110B
Colour (Liquid)	1	OTTAWA	STAILLON	2024-May-22	A-COL-01	SM 2120C
Cond/pH/Alk Auto (Liquid)	1	OTTAWA	SBOUDREAU	2024-May-22	COND-02/PH-02/A LK-02	SM 2510B/4500H/ 2320B
DOC/DIC (Liquid)	1	OTTAWA	VKASYAN	2024-May-22	C-OC-01	EPA 415.2
E.Coli m-TECH Media (Liquid)	2	BARRIE	NMUELLER	2024-May-17	EC-001	MECP E3371
ICP/OES (Liquid)	2	OTTAWA	NHOGAN	2024-May-22	D-ICP-01	SM 3120B
Ammonia (Liquid)	1	KINGSTON	JYEARWOOD	2024-May-21	NH3-001	SM 4500NH3
Total Coliforms (m-Endo Media)	2	BARRIE	NMUELLER	2024-May-17	TC-001	SM 9222B
Turbidity (Liquid)	2	OTTAWA	PLUSSIER	2024-May-21	A-TURB-01	SM 2130B

R.L. = Reporting Limit

NC = Not Calculated

Test methods may be modified from specified reference method unless indicated by an *



Michelle Dubien
Data Specialist

CADUCEON Environmental Laboratories Certificate of Analysis

Final Report
 REPORT No: 24-014150 - Rev. 0

Parameter	Units	R.L.	Limits	Client I.D.	TW2 - 1hr	TW2 - 6hr
					Sample I.D.	Sample I.D.
				Date Collected	24-014150-1	24-014150-2
				DWG	2024-May-16	2024-May-16
					-	-
Total Coliform	CFU/100mL	1	0	MAC	<2	<2
Background	CFU/100mL	1			12	6
E coli	CFU/100mL	1	0	MAC	0	0
Alkalinity(CaCO3) to pH4.5	mg/L	5	500	OG		193
TDS (Calc. from Cond.)	mg/L	3	500	AO		202
Conductivity @25°C	uS/cm	1				392
pH @25°C	pH units	-	8.5	OG		7.93
Colour	TCU	2	5	AO		<2
Turbidity	NTU	0.1	5	AO	22.4	7.2
Chloride	mg/L	0.5	250	AO		1.5
Nitrate (N)	mg/L	0.05	10.0	MAC	<0.05	<0.05
Nitrite (N)	mg/L	0.05	1.0	MAC	<0.05	<0.05
Ammonia (N)-Total (NH3+NH4)	mg/L	0.05				0.07
Dissolved Organic Carbon	mg/L	0.2	5	AO		1.2
Hardness (as CaCO3)	mg/L as CaCO3	0.02	100	OG		199
Calcium	mg/L	0.02				47.6
Magnesium	mg/L	0.02				19.4
Manganese	mg/L	0.001	0.05	AO		0.028
Sodium	mg/L	0.2	200, 20, 20	AO, WL, MAC	5.1	4.7
Free Chlorine (Client Data)	mg/L	-			0.5	0



Michelle Dubien
 Data Specialist

The analytical results reported herein refer to the samples as received and relate only to the items tested. Reproduction of this analytical report in full or in part is prohibited without prior consent from Caduceon Environmental Laboratories.

DWG - Drinking Water Guidelines

ODWS - Ontario Drinking Water Standards
 AO - Aesthetic Objectives
 IMAC - Interim Maximum Acceptable Concentration
 MAC - Maximum Acceptable Concentration
 ODWO - D-5-5 Objective
 OG - Operational Guidelines
 WL - Warning Level - Sodium Restricted Diets

Summary of Exceedances		
Aesthetic Objectives		
TW2 - 1hr	Found Value	Limit
Turbidity	22.4	5
TW2 - 6hr	Found Value	Limit
Turbidity	7.2	5
Maximum Acceptable Concentration		
TW2 - 1hr	Found Value	Limit
Total Coliform	<2	0
TW2 - 6hr	Found Value	Limit
Total Coliform	<2	0
Operational Guidelines		
TW2 - 6hr	Found Value	Limit
Hardness (as CaCO3)	199	100



Michelle Dubien
Data Specialist

Appendix F: Nitrate Impact Assessment

Scenario 1: No Pre-treatment

Number of Proposed Lots:	P	8		
Daily Effluent Flow / Lot:	F	1,000	L/day	Reference is made to MECP D-5-4
Subdivision Area:	A	30,000	m ²	
Infiltration Rate:	I	0.30	m/year	Reference to Section 2.3
Nitrate Loading / Dwelling:	N _s	40	g/day	
Background Nitrate:	N _b	0.11	mg/L	Highest recorded nitrate during pumping test

$$V_i = \frac{A * I}{365}$$

Groundwater Recharge:	V _i	25	m ³ /day	
-----------------------	----------------	----	---------------------	--

$$V_b = PF$$

Daily Sewage Volume:	V _b	8	m ³ /day	
----------------------	----------------	---	---------------------	--

$$RNC = \frac{V_i N_b + V_b N_s}{V_i V_b}$$

Resultant Nitrate Concentration at Site Boundary:	RNC	9.78	mg/L	
---	-----	------	------	--

Does the nitrate concentration at the downgradient property boundary meet the ODWS for nitrate (10 mg/L):	Yes
--	------------